

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	64	64		
20800150	TRENCH BACKFILL	CU YD	1	1		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.7	9.7		
40600300	AGGREGATE (PRIME COAT)	TON	46.2	46.2		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1410	1410		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	191	191		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	61	61		
40600990	TEMPORARY RAMP	SQ YD	76	76		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2116	2116		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2	2		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	20	20		
44005000	STABILIZED SHOULDER REMOVAL	SQ YD	11,194	11,194		
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	1507	1507		
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	92	92		
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	61	61		
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	59	59		
44213100	PAVEMENT FABRIC	SQ YD	153	153		
44213200	SAW CUTS	FOOT	5110	5110		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	544	544		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	5,597	5,597		
54248510	CONCRETE COLLAR	CU YD	0.47	0.47		
60100080	FRENCH DRAINS	CU YD	64	64		
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SQ YD	471	471		
60101605	PIPE DRAINS 4" (SPECIAL)	FOOT	137	137		
60251700	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 15 FRAME AND LID	EACH	1	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	20	20		
67000200	ENGINEER'S FIELD OFFICE, TYPE A	EACH	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2772	2772		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	73065	73065		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8426	8426		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24355	24355		
Z0017202	DOWEL BARS 1 1/2"	EACH	2840	2840		
Z0075300	TIE BARS	EACH	24	24		

**Specialty Items*

FILE NAME =	USER NAME = watersle	DESIGNED - ---	REVISED - ---
g:\p\work\NP\DOT\WATERSLE\d0174262\d876d71-shr-plan.dgn		DRAWN - ---	REVISED - ---
	PLOT SCALE = 103.1218 ' / IN.	CHECKED - ---	REVISED - ---
	PLOT DATE = 3/18/2018	DATE - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
735	55RS-5	MADISON	10	3
CONTRACT NO. 76D71				
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				

Rev.