

HOT-MIX ASPHALT RESURFACING SCHEDULE					
LOCATION	MILE STATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD) N70	HMA SURFACE COURSE MIX D, N70
		(TON)	(TON)	(TON)	(TON)
MAINLINE	0.00 TO 1.92	7.75	37.17	1387.7	2081.6
WOODBURN RD	0.82	0.01	0.06	2.1	3.1
GVILLO LN	1.15	0.01	0.05	1.9	2.8
BASSETT AVE	1.73	0.01	0.05	2.0	3.0
MAIN ST	1.85	0.04	0.20	7.6	11.3
SEILER RD	1.91	0.05	0.25	9.3	13.9
TOTAL:		7.9	37.8	1410	2116

BUTT JOINTS			
LOCATION	MI STA	PCC SURFACE REMOVAL	HMA SURFACE REMOVAL
		(SQ YD)	(SQ YD)
MAINLINE	0.00	61	
MAINLINE	1.92		61
WOODBURN RD - LEFT	0.82		19
GVILLO LN - RIGHT	1.15		17
BASSETT AVE - LEFT	1.73		18
MAIN ST - LEFT	1.85		17
MAIN ST - RIGHT	1.85		17
SEILER RD - LEFT	1.91		21
SEILER RD - RIGHT	1.91		21
TOTAL:		61	191

SHOULDER SCHEDULE								
LOCATION			LT/RT	BIT MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SHOULDERS, 6"	AGG WEDGE SHOULDERS, TYPE B,	STAB. SH. REMOVAL
STA	TO	STA		(TON)	(TON)	(SQ YD)	(TON)	(SQ YD)
0	TO	0.818	LT	0.45	2.16	1079.78	99.98	
0.822	TO	1.595	LT	0.43	2.04	1020.38	94.48	
0	TO	1.149	RT	0.63	3.03	1516.65	140.43	
1.151	TO	1.595	RT	0.24	1.17	586.05	54.27	
0	TO	1.59	LT					2798.5
0	TO	1.59	RT					2798.5
TOTAL:				1.8	8.4	4203	389	5597

TEMPORARY RAMPS		
LOCATION	MI STA	TEMPORARY RAMPS
		(SQ YD)
MAINLINE	0.00	10.1
MAINLINE	1.92	10.1
WOODBURN RD - LEFT	0.82	8.3
GVILLO LN - RIGHT	1.15	6.5
BASSETT AVE - LEFT	1.73	7.4
MAIN ST - LEFT	1.85	7.4
MAIN ST - RIGHT	1.85	7.4
SEILER RD - LEFT	1.91	9.2
SEILER RD - RIGHT	1.91	9.2
TOTAL:		76

FRENCH DRAIN SCHEDULE						
MILE STATION	LENGTH	WIDTH	DEPTH	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	FRENCH DRAINS	GEOTECHNICAL FABRIC FOR FRENCH DRAINS
	(FT)	(FT)	(FT)	(CU YD)	(CU YD)	(SQ YD)
0.210	15	34.0	1.0	18.9	18.9	136.0
1.250	12	34.0	1.0	15.1	15.1	113.3
1.420	12	34.0	1.0	15.1	15.1	113.3
1.850	15	27.0	1.0	15.0	15.0	108.0
TOTAL:				64	64	471

THERMOPLASTIC PAVEMENT MARKING					
LOCATION			LINE 4 INCH		
			SOLID WHITE	SOLID YELLOW	YELLOW SKIP DASH
STA	TO	STA	(FOOT)	(FOOT)	(FOOT)
0	TO	0.055	580	580	
0.055	TO	0.275	2320	1160	300
0.275	TO	1.92	17235		2180
SUB TOTAL:			20135	1740	2480
TOTAL:			24355		

NOTE: FRENCH DRAINS ARE LOCATED UNDER CLASS B PATCHES.