SUMMARY OF QUANTITIES

URBAN
1001. STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				I000	I000	I000
CODE NO	ITEM	UNIT		LOCATION 1	LOCATION 2	LOCATION 3
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	6	2	2
40600300	AGGREGATE (PRIME COAT)	TON	48	28	11	9
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1398	783	295	320
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	178			178
40600990	TEMPORARY RAMP	SQ YD	180	45	67	68
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	2936	1689	664	583
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	20665	18476		2189
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	7195	174	7021	
44200089	PAVEMENT PATCHING, TYPE I, 8 INCH	SQ YD	10			10
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	37			37
44200099	PAVEMENT PATCHING, TYPE III, 8 INCH	SQ YD	37			37
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SQ YD	77			77
44200128	PAVEMENT PATCHING, TYPE I, 11 INCH	SQ YD	10	10		
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	29			29
44200136	PAVEMENT PATCHING, TYPE III, 11 INCH	SQ YD	40	22	18	
44200138	PAVEMENT PATCHING, TYPE IV, 11 INCH	SQ YD	46		46	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.4	0.3	0.3
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4515	2772	1233	510
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13527	10956	2055	516
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	379	213	166	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	96	24	24	48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	530	308	137	85
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	125	83	42	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13527	10956	2055	516
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	379	213	166	
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	96	24	24	48
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	129	59	44	26
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	129	59	44	26

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				-------	-------	-------
CODE NO	ITEM	UNIT				

*Specialty Items

FILE NAME = c:\pw_work\PWIDOT\WATERSLE\d0175127\d876d85-sht-plan.dgn	USER NAME = watersle	DESIGNED - ---	REVISED - ---
		DRAWN - ---	REVISED - ---
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - ---	REVISED - ---
		DATE	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	DIST. 8 RES. 2010-6	ST. CLAIR	15	3
		CONTRACT NO. 76D85		