SUMMARY OF QUANTITIES

	SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
	CODE NO	ITEM	UNIT		ROADWAY I000-2A	LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F	OVERHEAD SIGNS Y002-1C
	81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	1500		1500		
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3479		1500	1979	
	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	8		8		
	83007400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. MAST ARM	EACH	6		6		
	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	33		33		
	83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	6		6		
	84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	10		10		
	84200804	REMOVAL OF POLE FOUNDATION	EACH	9		9		
*	86300400	CONTROLLER CABINET TYPE IV	EACH	1			1	
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2306			2306	
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2679			2679	
	87500900	TRAFFIC SIGNAL POST, 13 FT.	EACH	2			2	
	87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1			1	
	87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	2			2	
	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6			6	
	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3			3	
	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	39			39	
	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4			4	
	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6			6	
	88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	6			6	
	88600100	DETECTOR LOOP, TYPE I	FOOT	512			512	
	X0301271	REMOVE EXISTING UNDERDRAINS	FOOT	10024	10024			
	X0301894	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAIN	EACH	3	3			
	X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	5	5			
	X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1			
	X6013700	PIPE UNDERDRAIN REMOVAL (SPECIAL)	FOOT	265	265			
	X6013820	PIPE UNDERDRAIN OUTLET EXTENSION SPECIAL	EACH	3	3			
	X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	18			18	
	X7030070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	2791	2791			
	X7030076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	1667	1667			
*	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2800			2800	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
	Z0036200	PAINT CURB	FOOT	139	139			

*SPECIALTY ITEMS

FILE NAME = $FILE1$	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = $DATE$	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 5 OF 5 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-2RS-3	MADISON	231	8
		CONTRACT NO. 76D87		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		