



STA 1367+00  
 1 - LIGHT POLE, ALUMINUM, 35' MH, 10' MA  
 1 - LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT  
 1 - BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5" BOLT CIRCLE  
 5.5' - LIGHT POLE FOUNDATION, 24 INCH DIAMETER

STA 1369+00  
 1 - LIGHT POLE, ALUMINUM, 35' MH, 10' MA  
 1 - LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT  
 1 - BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5" BOLT CIRCLE  
 5.5' - LIGHT POLE FOUNDATION, 24 INCH DIAMETER

STA 1369+16  
 1 - REMOVAL OF LIGHTING UNIT, NO SALVAGE  
 1 - REMOVAL OF POLE FOUNDATION - CONCRETE

STA 1370+90  
 1 - REMOVAL OF LIGHTING UNIT, NO SALVAGE  
 1 - REMOVAL OF POLE FOUNDATION - CONCRETE

STA 1371+00  
 1 - LIGHT POLE, ALUMINUM, 35' MH, 10' MA  
 1 - LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT  
 1 - BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5" BOLT CIRCLE  
 5.5' - LIGHT POLE FOUNDATION, 24 INCH DIAMETER

1 - HEAVY DUTY HANDHOLE  
 INTERCEPT EXISTING CIRCUIT  
 AND SPLICE NEW CONDUCTOR  
 ABANDON FEED TO DOWNSTREAM POLES

STA 1370+10  
 DISCONNECT TRUSS NO 3

STA 1367+87.50 IL 3 =  
 STA 103+93.40 RAMP P8

STA 1373+22.21  
 END OF CONSTRUCTION

SEE INTERSECTION DETAILS  
 FOR INTERSECTION LAYOUT

**LEGEND**

- EXISTING LIGHTING CONTROLLER
- UNIT DUCT 2 #6 XLP, 1 #8 XLP, 1" PVC
- CONDUIT - SIZE SPECIFIED
- DISTRIBUTION TYPE, 2 OR 3
- EXISTING LIGHT & POLE
- NEW POLE & FIXTURE, 10' MAST ARM

LAST SAVED = 3/15/2010  
 PEN TABLE = VB.tbl  
 PLOT DRIVER = TR-Xerox6204-Te-File.plt

FILE NAME =	USER NAME = sdonahue	DESIGNED -	REVISED -
:\0906600\0906601\oad\plans\064.D87	087-Sht-Light-03.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0023' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/16/2010 4:42:35 PM	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**



**LIGHTING DETAILS**  
 ILLINOIS ROUTE 3

SCALE: 1" = 50' SHEET NO. 3 OF 4 SHEETS STA. 1364+00 TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-2RS-3	MADISON	231	82
CONTRACT NO. 76D87				
ILLINOIS FED. AID PROJECT				