SCALE IN FEET
0 50 100
N

REMOVE 4 HEADWALLS

PC Sta 21170+89.51
21170+00
FUTURE RAMP P1
RAMP E1
PC Sta 42171+00.98
Sta 42176+29.56
RAMP P5 LT
FAP 312 (IL 3)
IL RTE 3
PT Sta 21185+85.50
12+65+00
13+00
RAMP E6
24" RCP
12" CMP
PC Sta 23+59.66
INTERSTATE I-270 (FAI 270)
Sta 42224+35.00
41275+00
Sta 42172+60.01
PIPE UNDERDRAIN & HEADWALL REMOVAL
15' - 4" PIPE & HEADWALL
OVERHEAD SIGN TRUSS & FOUNDATION REMOVAL
GUARDRAIL REMOVAL
191'
GUARDRAIL REMOVAL
153'
CONSTRUCTION LIMITS
PIPE UNDERDRAIN & HEADWALL REMOVAL
12' - 4" PIPE & HEADWALL
Sta 42170+52.11
Sta 42170+49.93
PROPOSED RAMP P5
RAMP E5
31275+00
PIPE UNDERDRAIN & HEADWALL REMOVAL
17' - 4" PIPE & HEADWALL
CULVERT & HEADWALL REMOVAL
69' - 36" RCP & 2 HEADWALLS
DBLE PIPE UNDERDRAIN & DBL HEADWALL REMOVAL
17' - 4" PIPES & HEADWALLS
GUARDRAIL REMOVAL
116'
DBLE PIPE UNDERDRAIN & DBL HEADWALL REMOVAL
17' - 4" PIPES & HEADWALLS
GUARDRAIL REMOVAL
428'
PIPE UNDERDRAIN & HEADWALL REMOVAL
17' - 4" PIPE & HEADWALL
REMOVE TREES
31270+00
PCC Sta 31270+94.09
CONSTRUCTION LIMITS
REMOVE HEADWALL
RAMP P5
MATCH LINE STA 31268+00
31280+00
PT Sta 31280+70.08
16+00
13+45+00

LEGEND

EXISTING SHOULDER TO BE REMOVED

EXISTING ROADWAY PAVEMENT TO BE REMOVED

LAST SAVED = 3/14/2010
PEN TABLE = YR-10-01
PLOT DATE = I:\Xerox6204-To-File.plt

FILE NAME = I:\0906600\0906601\cad\t_plans\083_D876D87-Sht-Rem-09.dgn	USER NAME = sdonahue	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0023 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/16/2010 4:43:40 PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GONZALEZ COMPANIES

REMOVAL DETAILS
PROPOSED RAMP P5

SCALE: 1" = 50' | SHEET NO. 9 OF 10 SHEETS | STA. 31268+00 TO STA. 31280+70.08

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-2RS-3	MADISON	231	111
		CONTRACT NO. 76D87		
	ILLINOIS FED. AID PROJECT			