

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	101-2(RS-1,N-1)	ALEXANDER	189	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SUMMARY OF QUANTITIES

COUNTY:	ALEXANDER				
LOCATION:	RURAL				
ROUTE:	IL 146 (FAP 312)			IL 3 (FAP 14)	
FUNDING:	80% FEDERAL/ 20 % STATE			80% FEDERAL/20% STATE	
WORK TYPE:	ROADWAY	BOX CULVERT	LIGHTING	SIGNAL	ROADWAY
	STA 2+539.4 TO STA 6+100	SN 002-2002			STA 41+623.6 TO STA 42+225

CODE NUMBER	ITEM DESCRIPTION	CONSTRUCTION TYPE CODE:					UNIT	QUANTITY
		I000-2A	SFTY-2A	Y030-1E	Y031-1F	I000-2A		
M2020010	EARTH EXCAVATION					CU M	5,051.0	
M2040100	BORROW EXCAVATION					CU M	2,103.0	
M2080150	TRENCH BACKFILL					CU M	200.0	
M2500350	SEEDING, CLASS 7					HA	3.2	
M2500400	NITROGEN FERTILIZER NUTRIENT					KG	562.0	
M2500500	PHOSPHORUS FERTILIZER NUTRIENT					KG	421.0	
M2500600	POTASSIUM FERTILIZER NUTRIENT					KG	421.0	
M2500700	AGRICULTURAL GROUND LIMESTONE					M TON	14.0	
M2501010	SEEDING, CLASS 2 (MODIFIED)					HA	3.2	
M2510115	MULCH, METHOD 2					HA	6.4	
M2510630	EROSION CONTROL BLANKET					SQ M	6,000.0	
M2800250	TEMPORARY EROSION CONTROL SEEDING					KG	352.0	
M2800305	TEMPORARY DITCH CHECKS					METER	68.0	
M2800400	PERIMETER EROSION BARRIER					METER	36.0	
M3020456	PROCESSING MODIFIED SOIL 300MM					SQ M	49,710.0	
M3110100	SUB-BASE GRANULAR MATERIAL, TYPE A 100MM					SQ M	5,011.0	
M3112010	SUB-BASE GRANULAR MATERIAL, TYPE C					M TON	7,424.0	
M3120500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 100MM					SQ M	1,482.0	
M3510010	AGGREGATE BASE COURSE, TYPE A					M TON	387.0	
M3552200	HOT-MIX ASPHALT BASE COURSE					M TON	1,030.0	
M4020010	AGGREGATE SURFACE COURSE, TYPE A					M TON	162.0	
M4060115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)					LITER	100,758.0	
M4060300	AGGREGATE (PRIME COAT)					M TON	56.0	
M4060400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS					M TON	8.0	
M4060895	CONSTRUCTING TEST STRIP					EACH	3.0	
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT					SQ M	313.0	
M4060990	TEMPORARY RAMP					SQ M	341.0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

2 OF 5

SCALE: VERT.  
HORIZ.

DATE

DRAWN BY JCK  
CHECKED BY