DRAINAGE SCHEDULE

LOCATION STATION TO STATION	PRECAST CONCRETE BOX CULVERT 4' X 2'	PRECAST CONCRETE BOX CULVERT 4' X 3'	PIPE CULVERTS, CLASS A, TYPE 2, 30"	PIPE CULVERTS, CLASS D, TYPE 1, 36"	BOX CULVERT END SECTION, CULVERT NO. 1	BOX CULVERT END SECTION, CULVERT NO. 2	PRECAST REINFORCED CONCRETE FLARED END SECTION, 30"	END SECTIONS 36"	CONCRETE COLLAR	TRENCH BACKFILL	REMARKS
	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	CU YD	CY	
ILLINOIS 154 (FAP 841)											
74+64.52 LT TO 74+98.20 LT											
82+58.31 LT TO 82+59.32 LT		8			1					5	
94+49.6 LT TO 94+66.93 LT			26				1		0.37	7	
104+35.69 LT TO 104+35.79 LT	18					1				14	
106+58.5 LT TO 106+92.42 LT				34				2			
WHITE WALNUT RD. (FAU 9964)											
20+66.62 RT TO 20+95.28 RT											
TOTAL	18	8	26	34	1	1	1	2	0.37	26	

ENTRANCE AND SIDEROAD SCHEDULE

LOCATION STATION TO STATION	ENTRANCE TYPE	SURFACE TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SHOULDERS, TYPE B	AGGREGATE SURFACE COURSE, TYPE A 6"	REMARKS
			TON	TON	SQ YD	
ILLINOIS 154 (FAP 841)						
73+27	P.E.R.	AGG.	14	0.5		
74+82	P.E.L.	AGG.	10	0.5		
77+03	S.R.L.	HMA				
83+81	P.E.R.	AGG.	15	0.5		
84+63	P.E.R.	AGG.	14	0.5		
91+23	P.E.R.	AGG.	12	0.5		
96+45	F.E.R	AGG.				
102+59	P.E.R.	AGG.	12	0.5		
106+12	C.E.R.	AGG.	19	0.5		
106+75	F.E.L.	AGG.			39	
107+30	C.E.R.	AGG.	17	0.5		
WHITE WALNUT RD. (FAU 9964)						
22+15	F.E.L.	AGG.				
22+35	P.E.R.	AGG.	13	0.5		
SNOWY OWL RD.						
77+03	S.R.L.	BIT	22			
TOTAL			149	5.0	39	

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
ILLINOIS 154 (FAP 841)				
72+50 TO 109+80.15	5817	4363	1267	+ 3096
WHITE WALNUT RD. (FAU 9964)				
22+00 TO 22+45	873	655	2	+ 653
TOTALS	6690	5018	1269	+ 3749

25% Shrinkage Factor for Earth Excavation

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)	PAINT PAVEMENT MARKING: LINE 4" YELLOW (SOLID)	PAINT PAVEMENT MARKING: LINE 4" YELLOW (SKIP DASH)	PAINT PAVEMENT MARKING: LINE 4" WHITE (SOLID)	PAINT PAVEMENT MARKING: LINE 12" WHITE (SOLID)	PAINT PAVEMENT MARKING: LINE 12" YELLOW (SOLID)	THERMOPLASTIC PAVEMENT MARKING: LINE 24" (WHITE)	THERMOPLASTIC PAVEMENT MARKING: LETTERS AND SYMBOLS	REMARKS
		FOOT					FOOT	SQ FT	
IL 154 (FAP 841)									
72+50. TO 74+96.26	246		62						C/L
74+96.26 TO 76+16.26	120	240							C/L
76+16.26 83+81.29	765	3060				218			C/L & (0'-12') LT TWO DBL. SOLID
83+81.29 TO 85+08.92 BK	128	255		128					C/L & 12' LT
84+16.								27.4	
91+13.2 AH TO 92+70.55	157	315		157					C/L & 12' LT
92+09.								27.4	
94+20.78 TO 95+20.79	100	200		100					C/L & 12' LT
94+67								27.4	
95+20.79 TO 96+20.79	100	200							C/L
96+20.79 TO 101+00.	479	958	240						C/L & 12' LT
96+68								31.2	
98+63								31.2	
101+00. TO 102+00.	100	200							C/L
102+00. TO 103+00.	100	200		100					C/L & 12' LT
102+44								27.4	
103+81.29 TO 108+80.	499	1995				132			C/L & (0'-12') LT TWO DBL. SOLID
108+80. TO 109+80.15	100	200							C/L
72+50. LT TO 85+08.92 LT	1259			1259					LT EOP
72+50. RT TO 85+08.92 RT	1259			1259					RT EOP
91+13.2 LT TO 91+71.4 LT	58			58					LT EOP
91+13.2 RT TO 92+83.29 RT	170			170					RT EOP
93+53.27 RT TO 109+80.15 RT	1627			1627					RT EOP
94+01.3 LT TO 109+80.15 LT	1579			1579					LT EOP
WHITE WALNUT RD. (FAU 9964)									
20+24. LT TO 20+58.32 LT	34	142			87				HATCHED ISLAND AREA
20+24. RT TO 20+70.45 RT	46	139			103				HATCHED ISLAND AREA
20+24. LT TO 20+99.6 LT	76			172					NW RADIUS EOP LINE
20+24. RT TO 21+56.15 RT	132			171					NE RADIUS EOP LINE
20+34.31							12		
20+57.31							11		
20+57.31 TO 22+66.	209		52						C/L
20+99.6 LT TO 22+66. LT	166			166					
21+56.15 RT TO 22+66. RT	110			110					
PICK RD.									
9+37.8 TO 9+57.	19		4.8						
9+37.8 LT TO 9+88. LT	50			60					LT EOP
9+37.8 RT TO 9+88. RT	50			57					RT EOP
9+57							12		
TOTALS		8105	359	7173	190	350			
			15637		540		35	172	

FILE NAME = c:\pw_work\pwidot\greenleesm\dms51989\d078098_sht_misc.dgn	USER NAME = greenleesm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P RTE. 841	SECTION 108N-1	COUNTY PERRY	TOTAL SHEETS 76	SHEET NO. 9
		DRAWN -	REVISED -					CONTRACT NO. 78098		
	PLOT SCALE = 50.4587 ' / IN.	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			
	PLOT DATE = 1/27/2010	DATE -	REVISED -							