

**SUMMARY OF QUANTITIES**

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE	
				CONSTRUCTION TYPE CODE	
				SN 002-0001/2	SN 002-0003/4
				QUANTITY	QUANTITY
40600010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	80		
42001300	PROTECTIVE COAT	SQ YD	17771	12630	5141
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	762		
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	17644	12523	5121
48203100	HOT-MIX ASPHALT SHOULDERS	TON	64		
50102400	CONCRETE REMOVAL	CU YD	332.2	285.1	47.1
50157300	PROTECTIVE SHIELD	SQ YD	280	280	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	366	313.9	52.1
50300260	BRIDGE DECK GROOVING	SQ YD	16430	11648	4782
50300530	FLOOR DRAIN EXTENSION	EACH	462	390	72
<del>50500715</del>	<del>JACK AND REMOVE EXISTING BEARINGS</del>	<del>EACH</del>	<del>1</del>	<del>1</del>	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	65440	57210	8230
50800515	BAR SPLICERS	EACH	372	330	42
<del>52100020</del>	<del>ELASTOMERIC BEARING ASSEMBLY TYPE II</del>	<del>EACH</del>	<del>1</del>	<del>1</del>	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	891	711	180
<del>52100520</del>	<del>ANCHOR BOLTS, 1"</del>	<del>EACH</del>	<del>4</del>	<del>4</del>	
64200105	SHOULDER RUMBLE STRIP	FOOT	1520		
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	10		
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	0.5	0.5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	491	348	143
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12559	8584	3975
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4351	2978	1373
70400100	TEMPORARY CONCRETE BARRIER	FOOT	5362.5		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	5337.5		
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	12559		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	62	44	18
78300100	PAVEMENT MARKING REMOVAL	SQ FT	507		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	62	44	18
X0321468	PLUG EXISTING DECK DRAINS	EACH	372	292	80
X0323644	PAVEMENT MARKING GROOVING	FOOT	12559		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	12	12	
X7010820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	L SUM	1	0.5	0.5
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	17003	11966	5037
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	17003	11966	5037
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1.4		1.4
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1

\*Specialty Items

FILE NAME = c:\pwworkh\pwworkh\cornell\m\60170060\022-0001\0202-akt-misc.dgn

USER NAME = cornellm	DESIGNED -	REVISED -
PLOT SCALE = 50.0000 "/ IN.	DRAWN -	REVISED -
PLOT DATE = 2/22/2010	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	D9 BSMART 2010-1	ALEXANDER	25	3
CONTRACT NO. 78173			Rev.	
ILLINOIS FED. AID PROJECT				