

## CONCRETE PAVEMENT

LOCATION STATION TO STATION	PCC PAVEMENT 10" (JOINTED)	PCC DRIVEWAY PAVEMENT 7"	PROTECTIVE COAT*	SUB-BASE GRANULAR MATERIAL, TYPE A 4" *	SUB-BASE GRANULAR MATERIAL, TYPE A 6"
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
HALFWAY ROAD (INCLUDING FRONTAGE RD)					
LT. STA 405+78.02 TO STA 407+41.13	510		510		510
RT. STA 405+12.00 TO STA 407+27.00	1146		1146		1146
CEL STA 405+96.38		48	48	48	
IL 13 (CENTER)					
STA 1790+75.82 TO STA 1791+72.99	150		150		150
STA 1792+89.23 TO STA 1793+93.24	130		130		130
PROJECT TOTAL	1936	48	1984	48	1936

\* SEE CONCRETE CURB AND GUTTER SCHEDULE AND RETAINING WALL SCHEDULE FOR ADDITIONAL QUANTITY

## LIME MODIFIED SOILS

LOCATION STATION TO STATION	PROCESSING MODIFIED SOILS 12"	LIME	FOR INFO. ONLY WATER
	SQ YD	TON	UNIT
RAMP A			
STA 19+91.58 TO STA 43+25.07	7869	233.7	116.9
RAMP G			
STA 111+00 TO STA 156+01.79	14087	418.4	209.2
IL 13 (CENTER)			
STA 1778+92.35 TO STA 1799+10.65	6024	178.9	89.5
PROJECT TOTAL	27980	831.0	

## STRIP REFLECTIVE CRACK CONTROL

LOCATION STATION TO STATION	STRIP REFLECTIVE CRACK CONTROL TREATMENT
FOOT	
IL 13 (WB)	
STA 1793+97.93 TO STA 1799+11.21	2052
IL 13 (EB)	
STA 778+91.95 TO STA 790+75.91	1184
STA 1794+50.00 TO STA 1799+08.16	1374
PROJECT TOTAL	4610

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>CONCRETE PAVEMENT, LIME MODIFIED SOIL, AND STRIP CRACK CONTROL SCHEDULE</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			*	(X1-6-2)K-1;1X-1)R-4	WILLIAMSON	194	30
		PLOT SCALE = #SCALE#	REVISED -			* I-57/IL 13 (FAI 57/FAP 331)		CONTRACT NO. 78194		
		PLOT DATE = #DATE#	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.		
[ILLINOIS] FED. AID PROJECT										