STORM SEWERS

LOCATION STATION TO STATION	STORM SEWERS, CLASS A, TYPE 1	STORM SEWERS, CLASS A, TYPE 1	TRENCH BACKFILL *
	15"	18"	
	FOOT	FOOT	CU YD
IL 13 (CENTER)			
STA 1788+55.35	4		2.1
STA 1784+42 TO STA 1784+52	6		0
STA 1784+52 TO STA 1786+50	195		0
STA 1786+50 TO STA 1788+55	205		27.0
STA 1788+55 TO STA. 1790+95	240		67.6
RT. STA 1789+08 TO STA 1791+49	244		0.9
STA 1793+53 TO STA. 1793+76	22		5.7
STA 1793+76 TO STA 1795+43	172		40.6
STA 1795+45 TO STA 1797+95	248		47.5
STA 1797+97 TO STA 1799+07	109		12.0
STA 1799+07.20	7		0.8
HALFWAY ROAD			
RT. STA 405+46.82 TO STA 405+96.40		50	10.2
RT. STA 405+97.43 TO STA 406+44.17		50	0.3
RT. STA 406+45.83 TO STA 406+63.79		19	0.4
RT. STA 406+63.79 TO STA 1792+99.03		59	18.1
PROJECT TOTAL	1452	178	233.2

*SEE PIPE CULVERT SCHEDULE FOR ADDITONAL QUANTITY

MANHOLES

LOCATION STATION TO STATION	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES TO BE ADJUSTED WITH NEW TYPE 5 FRAME, CLOSED LID
	EACH	EACH	EACH
IL 13 (CENTER)			
RT. STA 1783+62.82		1	
RAMP G			
LT. STA 113+18.46	1		
HALFWAY ROAD			
RT. STA 407+15			1
PROJECT TOTAL	1	1	1

INLETS

LOCATION STATION	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	INLETS, SPECIAL, TYPE 3, 6'	INLET BOX,		INLETS TO BE RECONSTRUCTED WIITH TYPE 1 FRAME, CLOSED LID
			STANDARD 542526	STANDARD 542531	
	EACH	EACH	EACH	EACH	EACH
IL 13 (EB)					
STA 784+51.35	1				
STA 786+49.57	1				
STA 788+55.05		2			
STA 790+96.27		1			
STA 791+48.84		1			
STA 1793+49.78					1
STA 1793+73.20		1			
STA 1795+44.83		1			
STA 1797+95.13		1			
STA 1799+04.82		2			
RAMP A					
RT. STA 24+84.23	1				
LT. STA 26+00			1		
LT. STA 27+50				1	
HALFWAY ROAD					
RT. STA 406+45	1				
RT. STA 406+63.79		1			
FRONTAGE ROAD					
LT. STA 00+74.95		1			
RT. STA 00+66.52		1			
PROJECT TOTAL	4	12	1	1	1

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STORM SEWERS, MANHOLES, AND INLETS SCHEDULES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					*	(X1-6-2)K-1,(1X-1)R-4	WILLIAMSON	194	32
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -					*	I-57/IL 13 (FAI 57/FAP 331)	CONTRACT NO. 78194		
	PLOT DATE = $DATE$	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.		ILLINOIS	FED. AID PROJECT		