

## EARTHWORK

LOCATION STATION TO STATION	EARTH EXCAVATION	FOR INFORMATION ONLY				BORROW SWELL FACTOR	BORROW EXCAVATION	REMARKS
		AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE			
		CU YD	CU YD	CU YD	WASTE (+) SHORTAGE (-) CU YD			
IL 13 (CENTER) STA 1775+00 TO STA 1799+50	979	61.0	597	6668	-6071	0.18	7164	
RAMP A STA 19+91.58 TO STA 43+50	5635	74.9	4221	6137	-1916	0.18	2261	
RAMP G STA 110+50 TO STA 156+00	5982	70.8	4235	9594	-5359	0.18	6324	
I-57 (NB) STA 410+00 TO STA 417+77	-	-	-	27	-27	0.18	32	
PROJECT TOTAL	12596	-	-	-	-	-	15781	

## TREE REMOVAL

LOCATION STATION TO STATION	OFFSET FROM E.P.	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL ACRES	REMARKS
	FEET	UNIT	ACRE	
IL 13 (EB) STA 1794+38.62	78.4 RT	24	-	SWEETGUM
RAMP G STA 113+50 TO STA 120+91	-	-	0.91	SEE NOTE 1 THIS SHEET
STA 122+12 TO STA 134+11	-	-	0.52	SEE NOTE 1 THIS SHEET
STA 136+89 TO STA 140+91	-	-	0.08	SEE NOTE 1 THIS SHEET
STA 148+50 TO STA 152+83	-	-	0.13	SEE NOTE 1 THIS SHEET
PROJECT TOTALS	-	24	1.64	

NOTE: 1. "TREE REMOVAL, ACRE" CALCULATED FROM STATION TO STATION AND FROM TREE LINE TO CONSTRUCTION LIMITS.

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EARTHWORK AND TREE REMOVAL SCHEDULES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			*	(X1-6-2)K-1(1X-1)R-4	WILLIAMSON	194	36
		CHECKED -	REVISED -		SCALE:	* I-57/IL 13 (FAI 57/FAP 331)		CONTRACT NO. 78194		
		DATE -	REVISED -		SHEET NO. OF SHEETS	STA.	ILLINOIS FED. AID PROJECT		TO STA.	