

BILL OF MATERIALS

PAY ITEM	DESCRIPTION	UNIT	QUANTITY TOTALS
80300100	LOCATING UNDERGROUND CABLE	FOOT	390
81020600	CONDUIT PUSHED, 2 1/2" DIA., INTERMEDIATE METAL	FOOT	73
81020900	CONDUIT PUSHED, 4" DIA., INTERMEDIATE METAL	FOOT	228
81603070	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	7600
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6660
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 400 WATT	EACH	28
83010600	LIGHT POLE, ALUMINUM, 50 FT. MH, 15 FT. MAST ARM	EACH	28
83600357	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8"X8'	EACH	28
83800650	BREAKWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	112

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LIGHTING BILL OF MATERIALS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			*	(X1-6-2)K-1(1X-1)R-4	WILLIAMSON	194	111	
		PLOT SCALE = #SCALE#	CHECKED -			REVISIED -					
		PLOT DATE = #DATE#	DATE -			REVISED -	*	I-57/IL 13 (FAI 57/FAP 331)	CONTRACT NO. 78194		
					SCALE:	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		