

DATE _____ BY _____
 PLAN REVISIONS
 NO. _____ DATE _____
 NO. _____ DATE _____
 NO. _____ DATE _____

DATE _____ BY _____
 PROFILE REVISIONS
 NO. _____ DATE _____
 NO. _____ DATE _____
 NO. _____ DATE _____

FILE NAME = S:\STRUCT\1066009BureauCounty\Design\COVER1.C.dgn

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"		
STATION	EACH	REMARKS
CANAL STREET		
0+50	2	
PROJECT TOTAL	2	

54213669

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"		
STATION	EACH	REMARKS
CH 8		
25+92	2	
PROJECT TOTAL	2	

54213675

STEEL END SECTIONS 15"		
STATION	EACH	REMARKS
CH 8		
PER 39+37	2	
PER 39+52	2	
PER 40+55	2	
PROJECT TOTAL	6	

54213870

STEEL END SECTIONS 24"		
STATION	EACH	REMARKS
TOW PATH ROAD		
FER 1+24	2	ACROSS ENTRANCE
PROJECT TOTAL	2	

54213879

STORM SEWERS, CLASS A, TYPE 1 12"		
STATION	FOOT	REMARKS
TOW PATH ROAD		
3+49.01 TO 3+85.55	26	ACROSS ROAD
PROJECT TOTAL	26	

550A0050

PIPE UNDERDRAINS 6"		
STATION	FOOT	REMARKS
CH 8		
L 25+00 TO 25+84	84	
L 27+15 TO 30+75	360	
L 30+75 TO 33+90	315	
L 38+20 TO 41+00	280	
R 25+00 TO 25+84	84	
R 25+96 TO 27+50	154	
27+50 TO 29+00	1,200	CONTINGENCY ITEM FOR EX. EMBANKMENTS
R 27+54 TO 29+65	211	
R 30+35 TO 30+75	40	
R 30+75 TO 33+81	306	
R 38+82 TO 41+00	232	INCL RAD @ CANAL STREET
SUBTOTAL:	3,266	
TR 271A		
L 55+00 TO 59+11	411	
L 61+00 TO 65+30	430	
R 55+00 TO 59+11	411	
R 61+00 TO 65+30	430	
SUBTOTAL:	1,682	
TOW PATH ROAD		
L 0+13 TO 3+93	372	DRAINS INTO GUTTER OUTLET BOX
L 3+95 TO 4+85	90	DRAINS INTO 15" P.CUL
L 4+88 TO 5+65	76	DRAINS INTO 15" P.CUL
R 0+13 TO 3+87	401	
R 3+90 TO 4+79	90	
R 4+89 TO 5+58	69	
SUBTOTAL:	1,098	
PROJECT TOTAL	6,046	

60107700

PIPE UNDERDRAINS 6" (SPECIAL)		
STATION	FOOT	REMARKS
CH 8		
L 25+84	8	
L 30+75	16	2 PIPES @ 8'
L 38+20	11	
R 25+84	8	
R 27+50	8	
R 29+65	8	
R 30+75	20	2 PIPES @ 10'
R 39+20	6	
SUBTOTAL:	85	
TR 271A		
L 55+00	8	
L 61+00	7	
R 55+00	8	
R 61+00	7	
SUBTOTAL:	30	
TOW PATH ROAD		
R 3+87	8	
R 4+79	7	
R 5+58	8	
SUBTOTAL:	23	
		HEADWALLS INCIDENTAL TO PAY ITEM
PROJECT TOTAL	138	

60108200

CLASS SI CONCRETE (OUTLET)		
STATION	CU YD	REMARKS
TOW PATH ROAD		
L 4+30.21 TO 4+80.00	4.6	
PROJECT TOTAL	4.6	

60600095

CONCRETE GUTTER, TYPE A		
STATION	FOOT	REMARKS
TOW PATH ROAD		
L 0+91.33 TO 3+55.25	264	
PROJECT TOTAL	264	

60602500

GUTTER OUTLET (SPECIAL)		
STATION	EACH	REMARKS
TOW PATH ROAD		
L 3+55.25 TO 4+30.21	1	
PROJECT TOTAL	1	

60603400

STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS		
STATION	FOOT	REMARKS
CH 8		
L 32+54.36 TO 33+79.36	125	
L 38+31.86 TO 38+81.86	50	
R 31+93.14 TO 33+68.14	175	
PROJECT TOTAL	350	

63000001

WEATHERING STEEL TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT		
STATION	EACH	REMARKS
TR 271A		
L 58+53.57 TO 59+03.57	1	
L 61+46.28 TO 61+96.28	1	
R 58+03.78 TO 58+53.78	1	
R 60+96.43 TO 61+46.28	1	
PROJECT TOTAL	4	

63004001

TRAFFIC BARRIER TERMINAL, TYPE 6		
STATION	EACH	REMARKS
CH 8		
L 33+79.36 TO 34+25.00	1	
L 37+86.22 TO 38+31.86	1	
R 33+68.14 TO 34+13.78	1	
R 37+75.00 TO 38+20.64	1	
PROJECT TOTAL	4	

63100085

TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT		
STATION	EACH	REMARKS
CH 8		
L 32+04.36 TO 32+54.36	1	
L 38+81.86 TO 39+31.86	1	
R 31+43.14 TO 31+93.14	1	
R 38+20.64 TO 38+53.71	1	RADIUS
PROJECT TOTAL	4	

63100167

WILLET, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
 809 East Second Street Dixon, IL 61021
 Phone 815.284.3381 Fax 815.284.3385
 Design Firm # 184-00918
 www.willetthofmann.com

USER NAME =	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE =	CHECKED -	REVISED -
	DATE -	REVISED -

BUREAU COUNTY
BRIDGE REPLACEMENT
FAS 188 (C.H. 8) OVER IAIS RAILROAD & THE HENNIPEN CANAL

SCHEDULES OF QUANTITIES & GENERAL NOTES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00195-00-BR	BUREAU	127	10
STA.	TO STA.	CONTRACT NO. 87380		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT BRS-0188(118)				