

DATE
BY
DRAWN
CHECKED
DATE
NO.
DATE
NO.

DATE
BY
DRAWN
CHECKED
DATE
NO.
DATE
NO.

FILE NAME = S:\STRUCT\1066D05BureauCounty\Design\COVERT.C.dgn

TRAFFIC BARRIER TERMINAL, TYPE 5A		
STATION	EACH	REMARKS
TR 271A		
L & R 59+28.55 TO 59+41.78	2	
L & R 60+58.22 TO 60+71.45	2	
PROJECT TOTAL	4	

63100205*

STEEL PLATE BEAM GUARD RAIL REMOVAL		
STATION	FOOT	REMARKS
CH 8		
L 30+54 TO 33+94	340	
L 37+95 TO 39+33	138	
R 30+55 TO 33+94	339	
R 37+95 TO 38+33	38	
SUBTOTAL	855	
TR 271A		
L 55+92 TO 59+47	355	
L 60+53 TO 63+06	253	
R 55+96 TO 59+47	351	
R 60+53 TO 63+04	251	
SUBTOTAL	1,210	
PROJECT TOTAL	2,065	

63200305

REMOVAL AND REINSTALLATION OF EXISTING TERMINAL SECTION, SINGLE RAIL		
STATION	EACH	REMARKS
CH 8		
L 30+39.36 TO 30+89.36	1	
L 40+19.86 TO 40+69.86	1	
R 30+29.14 TO 30+79.14	1	
R 38+20.64 TO R 38+50	1	
PROJECT TOTAL	4	

63300315

REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARDRAIL		
STATION	FOOT	REMARKS
CH 8		
L 30+89.36 TO 33+79.36	290	
L 38+31.86 TO 40+19.86	88	
R 30+79.14 TO 33+68.14	289	
PROJECT TOTAL	667	

63300575

REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6		
STATION	EACH	REMARKS
CH 8		
L 33+79.36 TO 34+25.00	1	
L 37+86.22 TO 38+31.86	1	
R 33+68.14 TO 34+13.78	1	
R 37+75.00 TO 38+20.64	1	
PROJECT TOTAL	4	

63302700

CHAIN LINK GATES, 5' X 18' DOUBLE		
STATION	EACH	REMARKS
TOW PATH ROAD		
R 1+54	1	ACROSS FER 1+24
PROJECT TOTAL	1	

66407000

WOVEN WIRE GATES, 4' X 24' DOUBLE		
STATION	EACH	REMARKS
CH 8		
32+99 L 132'	1	
34+85 L 160'	1	
PROJECT TOTAL	2	

66502000

WOVEN WIRE FENCE, 4'		
STATION	FOOT	REMARKS
CH 8		
L 31+09.06 TO 32+34.00	178	
L 32+89.00 TO 35+27.24	230	DEDUCTIONS FOR GATE WIDTHS INCL.
PROJECT TOTAL	408	

66500105

BARBED WIRE FENCE, FIVE STRAND		
STATION	FOOT	REMARKS
CH 8		
R 27+04.82 TO 30+76.34	429	ALONG PROP. R.O.W.
R 30+94.51 TO 32+39.00	144	ALONG PROP. R.O.W.
R 32+87 TO 33+60.18	73	ALONG PROP. R.O.W.
PROJECT TOTAL	646	

66503200*

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
CH 8		
25+00 TO 41+00	291	4' - 40' SP (YELLOW) - 2 APPLICATIONS
SUBTOTAL	291	
TR 271A		
54+90.00 TO 65+30.00	189	4' - 40' SP (YELLOW) - 2 APPLICATIONS
SUBTOTAL	189	
PROJECT TOTAL	480	

70300100

SIGN PANEL - TYPE 1		
STATION	SQ FT	REMARKS
CH 8		
L 26+39	6.25	RI-1 TYPE 1 (STOP SIGN) @ 1400 N
SUBTOTAL	6.25	
TOW PATH ROAD		
L 0+25	6.25	RI-1 TYPE 1 (STOP SIGN) @ CH 8
R 3+46	7.07	W10-1 (RR X SIGN)
R 4+95	6.00	2- RI5-1 (RR X SIGNS)
R 4+95	2.25	RI5-2 (2 TRACKS SIGN) - 2 PCS
L 5+50	6.00	2- RI5-1 (RR X SIGNS)
L 5+50	2.25	RI5-2 (2 TRACKS SIGN) - 2 PCS
R 5+58	6.25	RI-2 TYPE 1 (YIELD SIGN) @ BIKE PATH
SUBTOTAL	36.07	
SHARED USE PATH		
R 6+50	6.25	W10-3 (RR X AHEAD LT)
R 7+61	6.25	RI-2 TYPE 1 (YIELD SIGN) @ BIKE PATH
L 8+44	6.25	W10-3 (RR X AHEAD RT)
SUBTOTAL	18.75	
CANAL STREET		
L 0+54	6.25	RI-1 TYPE 1 (STOP SIGN) @ CH 8
SUBTOTAL	6.25	
PROJECT TOTAL	67	

72000100

METAL POST - TYPE A		
STATION	FOOT	REMARKS
CH 8		
L 26+39	12	(STOP SIGN) @ 1400 N
SUBTOTAL	12	
TOW PATH ROAD		
L 0+25	12	(STOP SIGN) @ CH 8
R 3+46	12	(RR X SIGN)
R 4+95	14	(RR X SIGNS)
L 5+50	14	(RR X SIGNS)
R 5+58	12	(YIELD SIGN) @ BIKE PATH
SUBTOTAL	64	
SHARED USE PATH		
R 6+50	12	(RR X AHEAD LT)
R 7+61	12	(YIELD SIGN) @ BIKE PATH
L 8+44	12	(RR X AHEAD RT)
SUBTOTAL	36	
CANAL STREET		
L 0+54	12	(STOP SIGN) @ CH 8
SUBTOTAL	12	
PROJECT TOTAL	124	

72900100

PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS		
STATION	SQ FT	REMARKS
TOW PATH ROAD		
R 3+56	54	20' RR "X" (WHITE)
R 3+56	7.2	2 - 6' "R" (WHITE) @ 3.6 SF EA.
PROJECT TOTAL	61	

78001100

PAINT PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
CH 8		
25+00 TO 41+00	400	10' - 30' SP (YELLOW)
L 25+00 TO 26+48.85	212	EDGE LINE (WHITE)
L 26+67.47 TO 27+18.44	109	EDGE LINE (WHITE)
L 27+18.44 TO 41+00	1,382	EDGE LINE (WHITE)
R 25+00 TO 29+61.78	462	EDGE LINE (WHITE)
R 30+38.30 TO 38+48.61	916	EDGE LINE (WHITE)
R 38+67.67 TO 41+00	317	EDGE LINE (WHITE)
SUBTOTAL	3,798	
TR 271A		
54+90.00 TO 65+30.00	260	10' - 30' SP (YELLOW)
L 54+90.00 TO 65+30.00	1,040	EDGE LINE (WHITE)
R 54+90.00 TO 65+30.00	1,040	EDGE LINE (WHITE)
SUBTOTAL	2,340	
PROJECT TOTAL	6,138	

78001110

PAINT PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
CH 8		
L 26+53	10	STOP BAR @ 1400 N (WHITE)
SUBTOTAL	10	
TOW PATH ROAD		
R 3+31	8	STOP BAR BEFORE RR X PVT MKG (WHITE)
R 3+81	8	STOP BAR AFTER RR X PVT MKG (WHITE)
R 4+96	8	STOP BAR @ RR X SIGN (WHITE)
L 5+50	8	STOP BAR @ RR X SIGN (WHITE)
SUBTOTAL	32	
CANAL STREET		
L 0+54	10	STOP BAR @ CH 8 (WHITE)
SUBTOTAL	10	
PROJECT TOTAL	52	

78001180

WILLET, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
809 East Second Street, Dixon, IL 61021
Phone 815.284.3381 Fax 815.284.3385
Design Firm # 184-00918
www.willett-hofmann.com

USER NAME =	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE =	CHECKED -	REVISED -
	DATE -	REVISED -

BUREAU COUNTY
BRIDGE REPLACEMENT
FAS 188 (C.H. 8) OVER IAIS RAILROAD & THE HENNIPEN CANAL

SCHEDULES OF QUANTITIES & GENERAL NOTES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00195-00-BR	BUREAU	127	11
STA.	TO STA.	CONTRACT NO.	87380	
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT BRS-0188(118)				