

SUMMARY OF QUANTITIES					PARTICIPATING	NON-PARTICIPATING
					PAVEMENT	PAVEMENT
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE	
					J000 - 2A	Y060
	20800150	TRENCH BACKFILL	CU YD	1592		1592
	35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	4607	4607	
	35800100	PREPARATION OF BASE	SQ YD	4607	4607	
*	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	130	130	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	296	296	
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	125	125	
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	250	250	
	42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	4607	4607	
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1570	1570	
	42400800	DETECTABLE WARNINGS	SQ FT	160	160	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2964	2964	
	44000600	SIDEWALK REMOVAL	SQ FT	1158	1158	
*	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	417	417	
*	44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	4607	4607	
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	7	7	
	60255500	MANHOLES TO BE ADJUSTED	EACH	12	12	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	4	4	
	67100100	MOBILIZATION	LSUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LSUM	1	1	
△	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	630	630	
*	△	X0324585	SANITARY SEWER SERVICE REMOVAL AND REPLACEMENT	EACH	46	46
*	△	XX005891	WATER SERVICE RECONNECTIONS	EACH	14	14
*	Z0042300	PORTLAND CEMENT CONCRETE SIDEWALK CURB	FOOT	441	441	
*	△	Z0056700	SANITARY SEWER 4"	FOOT	230	230
*	△	Z0056800	SANITARY SEWER 6"	FOOT	230	230
*	△	Z0059700	SANITARY SEWER, TYPE 2 10"	FOOT	1366	1366
*	△	Z0060200	SANITARY SEWER, TYPE 2 24"	FOOT	50	50

* - INDICATES SPECIAL PROVISION
△ - INDICATES SPECIALTY ITEMS

FILE NAME = 10243-QUAN-01 - P01	USER NAME =	DESIGNED -- M FURLAN	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED HIGHWAY PLANS - BUCKLIN AVENUE CITY OF LASALLE SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -- M FURLAN	REVISED --					6106	08-00076-00-RP	LASALLE	10	3
	PLOT SCALE =	DRAWN -- JFA	REVISED --					CONTRACT NO. 87395				
	PLOT DATE = 4-2-2010	CHECKED -- BDB	REVISED --					SCALE: NONE	SHEET NO. 3 OF 10 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 3	ILLINOIS