F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36R-1,37R-2	TAZEWELL	449	19
STA 7+663.000		TO STA 9+899.166		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

PROPOSED PAVEMENT MARKING

LOCATION	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B	EPOXY PAVEMENT MARKING								RAISED REFLECTIVE PAVEMENT MARKERS		
	150MM	100MM			150MM	200MM	300MM			CRYSTAL	AMBER	
	WHITE SKIP-DASH LINE (METER)	YELLOW SOLID LINE (METER)	YELLOW SKIP-DASH LINE (METER)	YELLOW DOUBLE SOLID LINE (METER)	CROSS WALK (METER)	WHITE SOLID LINE (METER)	YELLOW DIAGONAL 6M C-C (METER)	WHITE DIAGONAL 6M C-C (METER)	LETTERS AND SYMBOLS (SQ. M)	ONE WAY (EACH)	ONE WAY (EACH)	TWO WAY (EACH)
7+225.000 TO 7+325.000 LT	0.0									4		
7+225.000 TO 7+325.000 RT	24.0									2		4
7+325.000 TO 7+500.000 LT	12.0	52.0	12.0						3	7		4
7+325.000 TO 7+500.000 RT	45.0	52.0	12.0							8	3	11
7+500.000 TO 7+675.000 LT	36.0	63.3	18.0	179.2		45.7	14.4		10	10	3	5
7+500.000 TO 7+675.000 RT	36.0	63.3	18.0	87.8		35.0	14.4			8	12	
7+675.000 TO 7+825.000 LT	37.5			350.0		45.7	63.8		1	7	12	
7+675.000 TO 7+825.000 RT	37.5			350.0			63.8			10	7	
7+825.000 TO 8+000.000 LT	33.0			181.8		43.0	35.5		3	5	7	4
7+825.000 TO 8+000.000 RT	33.0			267.8			35.5			18		
8+000.000 TO 8+175.000 LT	33.0					134.0			4	6		12
8+000.000 TO 8+175.000 RT	33.0			268.0						5		8
8+175.000 TO 8+350.000 LT	24.0	104.0	27.0						11	4		8
8+175.000 TO 8+350.000 RT	24.0	104.0	27.0							7		15
8+350.000 TO 8+525.000 LT	45.0	175.0	45.0						11	7		15
8+350.000 TO 8+525.000 RT	45.0	175.0	45.0							5		12
8+525.000 TO 8+700.000 LT	33.0	136.4	33.0						9	6		12
8+525.000 TO 8+700.000 RT	33.0	136.4	33.0							6		12
8+700.000 TO 8+875.000 LT	36.0	144.6	39.0						12	6		12
8+700.000 TO 8+875.000 RT	36.0	144.6	39.0							6		11
8+875.000 TO 9+050.000 LT	33.0	132.7	33.0						9	5		11
8+875.000 TO 9+050.000 RT	33.0	132.7	33.0							6		11
9+050.000 TO 9+225.000 LT	36.0	136.1	36.0						9	6		11
9+050.000 TO 9+225.000 RT	36.0	136.1	36.0							5		9
9+225.000 TO 9+400.000 LT	27.0	107.7	27.0						9	4		9
9+225.000 TO 9+400.000 RT	27.0	107.7	27.0							6		10
9+400.000 TO 9+575.000 LT	30.0	124.7	33.0						12	6		10
9+400.000 TO 9+575.000 RT	30.0	124.7	33.0							6		12
9+575.000 TO 9+750.000 LT	33.0	137.1	36.0						9	6		12
9+575.000 TO 9+750.000 RT	33.0	137.1	36.0							7		14
9+750.000 TO 9+925.000 LT	45.0	175.0	45.0						9	7		14
9+750.000 TO 9+925.000 RT	45.0	175.0	45.0							7		4
9+925.000 TO 10+100.000 LT	45.0	50.4	12.0							3		4
9+925.000 TO 10+100.000 RT	21.0	50.4	12.0							1		
10+100.000 TO 10+127.346 LT	6.0											
10+100.000 TO 10+127.346 RT	0.00											
OAKWOOD ROAD												
2+018.000 TO 2+097.731 LT					18.8							
2+018.000 TO 2+097.731 RT					46.0	34.7	4.8		3			
SUB-TOTAL	1,116	3,078	792	1,685	65	338	227	5	124	212	44	268
TOTAL QUANTITIES	1,116	5,555			65	338	232		124	524		

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
7+448.000 TO 7+820.000	70
7+820.000 TO 8+200.000	64
8+200.000 TO 8+540.000	56
8+540.000 TO 8+890.000	58
8+890.000 TO 9+260.000	62
9+260.000 TO 9+600.000	28
9+600.000 TO 9+899.166	26
TOTAL QUANTITY (EACH)	364

M7830100 PAVEMENT MARKING REMOVAL (SQ M)

DESCRIPTION	LOCATION
	7+225 TO 7+675
100mm DOUBLE SOLID YELLOW	59.9
100mm YELLOW SKIP DASH	1.0
150mm WHITE SKIP DASH	15.1
200mm WHITE SOLID	45.8
300mm WHITE	22.3
300mm YELLOW	35.3
LETTERS AND SYMBOLS	5.9
TOTAL QUANTITY (SQ M)	185

M7030220 TEMPORARY PAVEMENT MARKING - LINE 100MM

LOCATION	WHITE LINE (METER)	YELLOW LINE (METER)
STAGE I		
7+200.000 TO 7+550.000		
7+550.000 TO 7+900.000	474	474
7+900.000 TO 8+250.000	700	700
8+250.000 TO 8+600.000	700	700
8+600.000 TO 8+950.000	700	700
8+950.000 TO 9+300.000	700	700
9+300.000 TO 9+650.000	700	700
9+650.000 TO 10+000.000	498	498
SUBTOTAL STAGE I	4,472	4,472
STAGE IA		
9+650.000 TO 10+000.000	250	250
SUBTOTAL STAGE IA	250	250
STAGE II		
8+250.000 TO 8+600.000	650	650
8+600.000 TO 8+950.000	400	400
SUBTOTAL STAGE II	1,050	1,050
TOTAL QUANTITY (METER)	11,544	

M7030074 GROOVING FOR RECESSED PAVEMENT MARKING, 178MM

LOCATION	METER
7+225.000 TO 10+127.346	1,116
TOTAL QUANTITY (METER)	1,116

PAVEMENT MARKING TAPE, TYPE III & WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	M7030520 100MM WHITE (METER)	M7030520 100MM YELLOW (METER)	M7031000 AREA (SQ M)
STAGE I			
7+200.000 TO 7+550.000	325		32.5
7+550.000 TO 7+900.000	113	182	29.5
9+650.000 TO 10+000.000	202	202	40.4
10+000.000 TO 10+100.000	200	200	40.0
SUBTOTAL	840	584	142.4
STAGE IA			
9+650.000 TO 10+000.000	552	552	110.4
10+000.000 TO 10+100.000	200	200	40.0
SUBTOTAL	752	752	150.4
STAGE IIA			
7+200.000 TO 7+550.000	204	204	40.8
7+550.000 TO 7+900.000	700	700	140.0
7+900.000 TO 8+250.000	700	700	140.0
8+250.000 TO 8+600.000	50	50	10.0
8+600.000 TO 8+950.000	300	300	60.0
8+950.000 TO 9+300.000	700	700	140.0
9+300.000 TO 9+650.000	700	700	140.0
9+650.000 TO 10+000.000	700	700	140.0
10+000.000 TO 10+350.000	120	120	24.0
SUBTOTAL	4,174	4,174	834.8
STAGE IIB			
8+950.000 TO 9+300.000	71	71	14.2
9+300.000 TO 9+650.000	350	350	70.0
9+650.000 TO 10+000.000	63	63	12.6
SUBTOTAL	484	484	96.8
STAGE III			
7+900.000 TO 8+250.000	200	200	40
8+250.000 TO 8+600.000	700	700	140
8+600.000 TO 8+950.000	700	700	140
8+950.000 TO 9+300.000	700	700	140
9+300.000 TO 9+650.000	700	700	140
9+650.000 TO 10+000.000	500	586	110
SUBTOTAL	3,500	3,586	710
STAGE IV			
7+550.000 TO 7+900.000	306	306	61.2
7+900.000 TO 8+250.000	450	450	90
8+250.000 TO 8+600.000	392	392	78.4
8+600.000 TO 8+950.000	350	350	70
8+950.000 TO 9+300.000	350	484	83.4
9+300.000 TO 9+650.000	30	60	9
SUBTOTAL	1,878	2,042	392
TOTAL QUANTITIES	23,250		2,325

WHERE STAGE III TRAFFIC IS THE SAME AS STAGE II, REUSE PAVEMENT MARKINGS

WHERE STAGE IV TRAFFIC IS THE SAME AS STAGE III, REUSE PAVEMENT MARKINGS

70106800 CHANGEABLE MESSAGE SIGN

LOCATION	CAL MO
ENTIRE PROJECT	6
TOTAL QUANTITY (CAL MO)	6

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 8 - SEGMENT 2

SCHEDULE OF QUANTITIES - 5

SCALE: NTS DRAWN BY: RDT

DATE: DECEMBER, 2003 CHECKED BY: PK