

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				70% FED 30% STATE (IL RT 8)	70% FED 30% CITY (SUMMIT)	70% FED 21% STATE 9% CITY (DRAINAGE)	70% FED 15% STATE 15% CITY (SIGNALS)	70% FED 15% STATE 15% CITY (SIDEWALK)
				J000-2A	I000-1A	Y031-1F	SFTY 1-B	
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1589		1589			
40603560	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	138	138				
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	37	37				
42000501	PORTLAND CEMENT CONCRETE PAVEMENT, 10" (JOINTED)	SQ YD	7792	7792				
42001300	PROTECTIVE COAT	SQ YD	7792	7792				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	425		425			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1148	486	662			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	6536		845			5,691
42400300	PORTLAND CEMENT CONCRETE SIDEWALK, 6 INCH	SQ FT	74	74				
42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	3524		307			3,217
42400440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	626					626
42400800	DETECTABLE WARNINGS	SQ FT	116	116				
44000100	PAVEMENT REMOVAL	SQ YD	7,059	5,071	1988			
44000198	HOT - MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,139	1,139				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3,000	2,038	962			
44000300	CURB REMOVAL	FOOT	349	199	150			
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	313	313				
44004000	PAVED DITCH REMOVAL	FOOT	22	22				
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	2	2			
50105220	PIPE CULVERT REMOVAL	FOOT	1,547	888	659			
50800105	REINFORCEMENT BARS	POUND	36,200		36,200			
50901760	PIPE HANDRAIL	FOOT	100	100				
54003000	CONCRETE BOX CULVERTS	CU YD	198.4		198.4			
542A1087	PIPE CULVERTS, CLASS A, TYPE 2 42"	FOOT	111		111			
542A4057	PIPE CULVERTS, CLASS A, TYPE 6 72"	FOOT	304			304		
542A4663	PIPE CULVERTS, CLASS A, TYPE 7 48"	FOOT	74			74		
542D0220	PIPE CULVERT, CLASS D, TYPE 1 15"	FOOT	143	143				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	1	3			
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2				
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	4		4			
54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	1		1			
54215472	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 72"	EACH	1		1			
54215550	METAL END SECTIONS 15"	EACH	4	4				
54248500	CONCRETE HEADWALLS	CU YD	16.9			16.9		
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	813	13	800			
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	107	107				
550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	216		216			
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	168	168				
550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	62			62		

\* SPECIALTY ITEM