

| CODE NUMBER | PAY ITEM   | UNIT  | TOTAL QUANTITY | CONSTRUCTION TYPE CODE                      |                                 |  |  |  |
|-------------|--|-------|----------------|---|---------------------------------|--|--|--|
|             |  |       |                | 70% FED<br>30% STATE<br>(L RT B)<br>J000-2A | 70% FED<br>30% CITY<br>(SUMMIT) | 70% FED<br>21% STATE<br>9% CITY<br>(DRAINAGE)<br>I000-1A | 70% FED<br>15% STATE<br>15% CITY<br>(SIGNALS)<br>Y031-1F<br>2533 | 70% FED<br>15% STATE<br>15% CITY<br>(SIDEWALK)<br>SFTY 1-B |
| 87301255    | * ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C           | FOOT  | 2533           |   |                                 |  |  |  |
| 87301515    | * ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR      | FOOT  | 1770           |   |                                 |  | 1770   |  |
| 87702990    | * STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 54 FT.   | EACH  | 1              |   |                                 |  | 1  |  |
| 87703020    | * STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 58 FT.   | EACH  | 2              |   |                                 |  | 2  |  |
| 87703030    | * STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 60 FT.   | EACH  | 1              |   |                                 |  | 1  |  |
| 87800200    | * CONCRETE FOUNDATION, TYPE D                            | FOOT  | 3.5            |   |                                 |  | 3.5  |  |
| 87800415    | * CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER          | FOOT  | 78             |   |                                 |  | 78   |  |
| 88030020    | * SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED  | EACH  | 8              |   |                                 |  | 8  |  |
| 88030070    | * SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED   | EACH  | 4              |   |                                 |  | 4  |  |
| 88030080    | * SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED  | EACH  | 4              |   |                                 |  | 4  |  |
| 88102820    | * PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2 FACE, 8M | EACH  | 4              |   |                                 |  | 4  |  |
| 88200310    | * TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC     | EACH  | 12             |   |                                 |  | 12   |  |
| 88500100    | * INDUCTIVE LOOP DETECTOR                                | EACH  | 12             |   |                                 |  | 12   |  |
| 88600100    | * DETECTOR LOOP, TYPE 1                                  | FOOT  | 1649           |   |                                 |  | 1649   |  |
| 88700200    | * LIGHT DETECTOR   | EACH  | 2              |   |                                 |  | 2  |  |
| 88700300    | * LIGHT DETECTOR AMPLIFIER                               | EACH  | 1              |   |                                 |  | 1  |  |
| 88800100    | * PEDESTRIAN PUSH-BUTTON                                 | EACH  | 8              |   |                                 |  | 8  |  |
| 89000100    | * TEMPORARY TRAFFIC SIGNAL INSTALLATION                  | EACH  | 1              |   |                                 |  | 1  |  |
| 89502380    | * REMOVE EXISTING HANDHOLE                               | EACH  | 1              |   |                                 |  | 1  |  |
| 89502382    | * REMOVE EXISTING DOUBLE HANDHOLE                        | EACH  | 1              |   |                                 |  | 1  |  |
| 89502385    | * REMOVE EXISTING CONCRETE FOUNDATION                    | EACH  | 1              |   |                                 |  | 1  |  |
| X0321556    | SANITARY MANHOLES TO BE ADJUSTED                         | EACH  | 12             | 5   | 7                               |  |  |  |
| X0322468    | GAS VALVE TO BE ADJUSTED                                 | EACH  | 1              | 1   |                                 |  |  |  |
| X0322869    | REMOVE TIMBER RETAINING WALL                             | L SUM | 1              |   | 1                               |  |  |  |
| X0323381    | STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 12"      | FOOT  | 268            |   | 268                             |  |  |  |
| X0323382    | STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 15"      | FOOT  | 83             | 83  |                                 |  |  |  |
| X0323383    | STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 18"      | FOOT  | 142            | 142   |                                 |  |  |  |
| X0323863    | STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 12"      | FOOT  | 75             | 75  |                                 |  |  |  |
| X0323889    | STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 18"      | FOOT  | 254            | 234   | 20                              |  |  |  |
| X0324134    | * BATTERY BACKUP SYSTEM WITH CABINET                     | EACH  | 1              |   |                                 |  | 1  |  |
| X0696100    | PARKING BLOCKS   | EACH  | 15             | 15  |                                 |  |  |  |
| X0712400    | TEMPORARY PAVEMENT                                       | SO YD | 891            | 891   |                                 |  |  |  |
| X5510100    | STORM SEWER REMOVAL                                      | FOOT  | 335            |   | 335                             |  |  |  |
| X6020065    | INLETS, TYPE G-1, DOUBLE (SPECIAL)                       | EACH  | 5              |   | 5                               |  |  |  |
| X6020080    | INLETS, TYPE G-1, DOUBLE                                 | EACH  | 3              | 3   |                                 |  |  |  |
| X6020088    | MANHOLES, TYPE A, 8"-DIAMETER, TYPE 1 FRAME, CLOSED LID  | EACH  | 1              | 1   |                                 |  |  |  |
| X6020098    | MANHOLES, TYPE A, 9"-DIAMETER, TYPE 1 FRAME, CLOSED LID  | EACH  | 1              | 1   |                                 |  |  |  |
| X7030074    | GROOVING FOR RECESSED PAVEMENT MARKING 7"                | FOOT  | 360            | 360   |                                 |  |  |  |
| X8730027    | * ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C         | FOOT  | 527            |   |                                 |  | 527  |  |

\* SPECIALTY ITEM