



KEYED NOTES:

- 1 NEW 250W HPS LUMINAIRE MOUNTED ON NEW 40 FT. POLE.
- 2 2-1/C NO. 6, 600 XLP, 1-1/C NO. 6 G., 600 XLP, 2" PVC CONDUIT IN TRENCH.
- 3 NEW 400W HPS LUMINAIRE MOUNTED 45 FT. ABOVE FINISHED GRADE ON TRAFFIC SIGNAL POLE.
- 4 EXISTING CONTROLLER WITH 4 EXISTING 30A/2P CIRCUIT BREAKERS, SEE STAGE 3 DRAWINGS.
- 5 4-1/C NO. 6, 600 XLP, 1-1/C NO. 6 G., 600 XLP, 2" PVC CONDUIT IN TRENCH.

| | | | | | | | | | | | | |
|---|------------------------|-----------------|-----------|---|--|--------------------------|--------------------------|---|----------------|--------------|-----------|----|
| FILE NAME = | USER NAME = Ander00846 | DESIGNED - PJG | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | LIGHTING PLAN NORTHMOOR AND SHERIDAN ROAD STAGE 1 IMPROVEMENT | | F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| I:\09Jobs\09L0027\CADD\Elec\Sheet\0-201.dgn | | DRAWN - ANC | REVISED - | | SCALE: 1"=20' | SHEET NO. 2 OF 10 SHEETS | STA. 85+00 TO STA. 89+00 | 6647 | 08-00302-00-PV | PEORIA | 102 | 63 |
| | | CHECKED - RDN | REVISED - | | | | | 6595 | 09-00047-01-PV | | | |
| | | DATE - 03/19/10 | REVISED - | | | | | CONTRACT NO. 89523 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT M-5093(135) | | | | |