

| ROUTE NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------------|----------------|----------------------------------|--------------|-----------|
| FAU 6576 | 09-00177-00-SP | PEORIA | 33 | 23 |
| FED. ROAD DIST. NO. 7 | | ILLINOIS PROJECT: HSP 5093 (191) | | |
| CONTRACT NO. 89561 | | | | |



PLACE 17 CHEVRONS (W1-8) EACH
DIRECTION THROUGH CURVE
SPACED AT 70' CENTERS
MILE 2.27 TO MILE 2.44

PLACE OBJECT MARKER
SIGN AT UTILITY POLE

207

123

MILE
2.25

KICKAPOO CREEK ROAD

KICKAPOO CREEK

PROP. STEEL PLATE BEAM GUARDRAIL, TY A, 9' POST - 625 FOOT
TBT TYPE 1 (SPL) TANGENT - 2 EACH
TERMINAL MARKER - DIRECT APPLIED - 2 EACH
MONODIRECT GUARDRAIL REFLECTORS - 7 EACH
(TOTAL GUARDRAIL LENGTH = 625 FOOT)
MILE 2.32 TO MILE 2.44

GUARDRAIL AND NEW SIGN LOCATION PLAN
NOT TO SCALE