GENERAL NOTES

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPER-SEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY

G.N.-107.12

THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE LOCAL RAILROAD CONTACT IS:

Mr. Ben Crossman Roadmaster CSX Transportation 564 CSX Lane Danville, IL 61834 (217) 442-0126

SPECIAL ATTENTION IS CALLED TO ARTICLE 107.12 REGARDING RAILROAD FLAGGERS. THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE RAILROAD CONTACT PERSON FOR FLAGGERS IS:

Dave Fette 1717 Dixie Hwy Suite 400 Fort Wright, KY 41011 859-344-8137

G.N.-406

THE QUANTITIES INCLUDED IN THE PLANS FOR HOT

MIX ASPHALT RESURFACING ARE INTENDED TO GIVE THE COVERAGE
SHOWN ON THE TYPICAL CROSS SECTIONS. IT IS NOT INTENDED

TO INCREASE THE THICKNESS OF THE BITUMINOUS MIXTURE IN

ORDER TO USE ALL OF THE QUANTITIES INCLUDED IN THE CONTRACT.

G.N.-406H

MIXTURE REQUIREMENTS

The following mixture requirements are applicable for this project:

Location(s):	FAP 812				
Mixture Use(s):	LEVEL BINDER	SURFACE, INCIDENTAL & PARTIAL			
***************************************		DEPTH PATCHING			
AC/PG:	PG 64-22	PG 64-22			
RAP %: (Max)**	25	15			
Design Air Voids:	4% @ Ndes =50	4% @ Ndes =50			
(Gradation Mixture)	IL 9.5	IL 9.5			
Friction Aggregate:	Mix C	Mix C			

406.05B

ALL LEVELING BINDER OR BINDER SHALL BE GIVEN A FOG COAT OF PRIME BEFORE THE SURFACE COURSE IS PLACED WHEN DIRECTED BY THE ENGINEER. THE FOG COAT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER GALLON FOR BITUMINOUS MATERIAL (PRIME COAT) AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-408B

THE INCIDENTAL HOT-MIX ASPHALT SURFACING SHALL BE COMPACTED AS REQUIRED BY THE SPECIFICATIONS FOR DESIGN NUMBER OF GYRATIONS BEING USED, AT THE FOLLOWING LOCATIONS:

SIDE ROADS						
OFFSET	CL STATION	NAME				
LT.	55+97.5	600 N				
RT.	55+95.5	600 N				
· LT.	108+61.6	500 N				
RT.	108+35.4	500 N				
LT.	161+03.0	400 N				
RT.	161+25.0	400 N				
LT.	213+60.0	300 N				
RT.	213+84.0	300 N				
LT.	264+14.0	200 N				
LT.	318+68.0	100 N				
RT.	319+17.0	100 N				

G.N.-442B -- PATCHING SCHEDULES

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N.-442C -- PARTIAL DEPTH PATCHING DIMENSIONS

FOR PARTIAL DEPTH PAVEMENT PATCHING, THE MINIMUM SIZE OF ANY PATCH SHALL BE 4 FT BY HALF LANE WIDTH. IF THE REPAIR OF ANY SMALLER AREAS IS REQUIRED, THAT WORK SHALL BE DESIGNATED AS "PAVEMENT CLEANING" AND WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.

G.N.-667

THE RESIDENT ENGINEER SHALL CONTACT THE PROGRAM DEVELOPMENT CHIEF OF SURVEYS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE FOR INSTRUCTION AS TO SETTING OF TEMPORARY OR PERMANENT TIES FOR CENTERLINE ALIGNMENT CONTROL SURVEY MARKERS (PC'S, PT'S, AND PI'S). PROJECT IMPLEMENTATION PERSONNEL WILL BE RESPONSIBLE FOR SETTING THESE MARKERS.

G.N.-703A

SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO THE PAVEMENT AFTER ANY OF THE FOLLOWING: COLD MILLING AND/OR PLACING BITUMINOUS MATERIALS (PRIME COAT), LEVELING BINDER (MACHINE METHOD), BINDER AND SURFACE COURSES. SHORT TERM PAVEMENT MARKING PLACED ON THE SURFACE, SHALL COINCIDE WITH THE FINAL PAVEMENT STRIPING. SHORT TERM PAVEMENT MARKING PLACED PRIOR TO THE SURFACE SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. USE 4 FEET PER 40 FEET (OR 10% PER STATION).

G.N.-781

RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPENCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9 m) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

NO COMMITMENTS

FILE NAME =	USER NAME = leroymo	DESIGNED -	REVISED -	
c:\pw_work\pwidot\leroyma\d0175388\d950	1698.dgn	DRAWN -	REVISED -	
	PLOT SCALE = 40.0000 '/ IN.	CHECKED -	REVISED -	
	PLOT DATE = 3/8/2010	DATE -	REVISED -	

STATI	E 01	FILLINOIS	
DEPARTMENT	OF	TRANSPORTATION	

GENERAL NOTES					F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET		
							812	(25,24)RS-1	PIATT	28	3
									CONTRAC	NO.	90915
LE:	SHEET	NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. AI	D PROJECT		