

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	81
20200100	EARTH EXCAVATION	CU YD	7,823
20400800	FURNISHED EXCAVATION	CU YD	9,396
20800150	TRENCH BACKFILL	CU YD	494
• 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	5.6
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	560
• 28000305	TEMPORARY DITCH CHECKS	FOOT	932
28000400	PERIMETER EROSION BARRIER	FOOT	6,808
28000500	INLET AND PIPE PROTECTION	EACH	7
28100207	STONE RIPRAP, CLASS A4	TON	32
• 35100100	AGGREGATE BASE COURSE, TYPE A	TON	5,506
• 40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	107
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,745
40600300	AGGREGATE (PRIME COAT)	TON	11
40600895	CONSTRUCTION TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT	SQ YD	418
40600990	TEMPORARY RAMP	SQ YD	49
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	3,221
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,429
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,668
• 50105220	PIPE CULVERT REMOVAL	FOOT	273
50300225	CONCRETE STRUCTURES	CU YD	3.4
50800105	REINFORCEMENT BARS	POUND	216
50901760	PIPE HANDRAIL	FOOT	18
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	124
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	120
542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36"	FOOT	100
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	72
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1
• 61139900	STORM SEWER, SPECIAL 6"	FOOT	200
• 61140000	STORM SEWER, SPECIAL 8"	FOOT	200
• 61140200	STORM SEWER, SPECIAL 12"	FOOT	200
67100100	MOBILIZATION	L SUM	1
• 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,362
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	17,019
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	450
△ 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	17,019
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1

• SEE SPECIAL PROVISIONS      △ SPECIALTY ITEMS

CONSTRUCTION TYPE CODE: I000-2A

FILE NAME = V:\Transportation\2839\28390001.dgn	USER NAME = jolson	DESIGNED - JRB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>LITERBERRY-PRENTICE ROAD (CH 19) SUMMARY OF QUANTITIES</b>		F.A.S. RTE. 611	SECTION 05-00093-03-FP	COUNTY MORGAN	TOTAL SHEETS 31	SHEET NO. 3
PLOT SCALE = 50,0000' / IN.	CHECKED - JRB	REVISED -	SCALE: N/A		SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 3535			
PLOT DATE = 2/26/2010	DATE - 1/18/2010	REVISED -					ILLINOIS FED. AID PROJECT				