

ROUTE	SECTION	COUNTY	SHEET NO.	TOTAL SHEETS
FAS 2797	07-00081-00-RS	CLAY	2	8
FEDERAL ROAD DISTRICT 7		ILLINOIS	FEDERAL AID PROJ.	
CONTRACT NO. 95625				

GENERAL NOTES

- 1) THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, SPECIAL PROVISIONS AND THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007.
- 2) AT LEAST 48 HOURS BEFORE ANY EXCAVATING, CALL J.U.L.I.E. 1-800-892-0123 FOR UTILITY LOCATION INFORMATION.
- 3) TRANSVERSE CONSTRUCTION JOINTS SHALL REQUIRE #5 SMOOTH BARS 18" LONG AT 12" CENTERS. IT IS ANTICIPATED THAT TRANSVERSE CONSTRUCTION JOINTS WILL BE REQUIRED AT THE END OF EACH DAYS POUR AND AT BLOCKOUTS FOR ACCESS TO DRIVEWAYS AND SIDEROADS.
- 4) THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE ENGINEER AS TO THE LOCATION OF CONSTRUCTION JOINTS.
- 5) #5 DEFORMED REBAR 30" LONG AT 30" CENTERS SHALL BE INSTALLED AT ALL LONGITUDINAL CONSTRUCTION JOINTS, EXCEPT THE CENTERLINE JOINT WHERE NO TIE BARS WILL BE REQUIRED.

UTILITIES

(FOR INFORMATION ONLY)

FRONTIER COMMUNICATIONS
801 WEST JACKSON ST.
ALTA MONT, IL. 62411
618-483-6391

WABASH TELEPHONE COOP.
210 S. CHURCH ST.
LOUISVILLE, IL 62858
618-665-3311

PIPELINK MAINTENANCE (BP OIL)
PO BOX 99
BROOKLYN, IN. 46111
765-342-7444

NORTHEAST MARION COUNTY WATER
5329 KINMUNDY RD
SALEM, IL. 62881
618-547-9887

MARATHON ASHLAND PIPELINE
8762 U.S. HWY. 51
VERNON, IL. 62892
618-432-7223

CLAY ELECTRIC COOP
7784 OLD HWY 50
FLORA, IL. 62839
618-662-2171

CLASS C PATCHES, 8 INCH (PCC)					
STATION TO STATION	LT / RT	WIDTH	TYPE II	TYPE III	TYPE IV
			SQ. YDS.	SQ. YDS.	SQ. YDS.
166+88 TO 168+14	RT	5.5			77.0
186+00 TO 186+31	RT	5.5		18.9	
187+37 TO 188+79	RT	11.0			173.6
189+56 TO 190+49	RT	11.0			113.7
193+00 TO 193+54	RT	11.0			66.0
198+34 TO 198+94	RT	5.5			36.7
207+43 TO 207+98	RT	11.0			67.2
389+79 TO 390+61	RT	11.0			100.2
397+55 TO 398+26	RT	11.0			86.8
399+15 TO 399+32	LT	5.5	10.4		
404+87 TO 406+26	RT	11.0			169.9
408+02 TO 408+21	LT	5.5	11.6		
414+82 TO 415+22	RT	5.5		24.4	
418+53 TO 419+33	RT	5.5			48.9
TOTALS			22.0	43.3	940.0

NOTES

- 1) THE ACTUAL SIZE AND LOCATION OF PATCHES WILL BE DETERMINED IN THE FIELD BY THE ENGINEER AFTER COMPLETION OF THE MILLING PROCESS.
- 2) ALL PATCHES SHALL BE LAYED OUT AS EITHER 1/2 LANE WIDTH (5.5') OR FULL LANE WIDTH (11.0') SO THAT LONGITUDINAL CONSTRUCTION JOINTS CLOSELY MATCH WITH LONGITUDINAL CONTRACTION / CONSTRUCTION JOINTS OF THE PCC PAVEMENT ABOVE.

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY
X4020900	AGGREGATE SURFACE COURSE, TYPE B (SPECIAL)	SQ YD	1,613.3
44201329	CLASS C PATCHES, TYPE II, 8 INCH	SQ YD	22.0
44201333	CLASS C PATCHES, TYPE III, 8 INCH	SQ YD	43.3
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	940.0
67100100	MOBILIZATION	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
Δ * 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	19,120
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	12.4
* X4400157	HMA SURFACE REMOVAL 2", (SPECIAL)	SQ YD	103,674
* XX005348	AGGREGATE SHOULDERS (SPECIAL)	FOOT	83,778
Z0055300	RUMBLE STRIP	EACH	6
* XX007371	PORTLAND CEMENT CONCRETE PAVEMENT, FURNISHED	CU YD	14,539
* XX007372	PORTLAND CEMENT CONCRETE PAVEMENT, 5" PLACEMENT	SQ YD	103,232
* XX007374	PORTLAND CEMENT CONCRETE PAVEMENT, 7" PLACEMENT	SQ YD	872.3

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

PAINT PAVEMENT MARKING LINE - 4"

CENTERLINE (DASHED)		NORTHBOUND NO PASSING		SOUTHBOUND NO PASSING	
STA. TO STA.	QUANTITY	STA. TO STA.	QUANTITY	STA. TO STA.	QUANTITY
-0+10 TO 117+29	2,940 FT	69+17 TO 75+17	600 FT	80+24 TO 86+24	600 FT
135+11 TO 422+71	7,190 FT	106+17 TO 135+11	2,894 FT	117+29 TO 146+11	2,882 FT
		324+82 TO 334+22	940 FT	336+11 TO 346+85	1,074 FT
TOTAL 10,130 FT		TOTAL 4,434 FT		TOTAL 4,556 FT	