

ROUTE NO	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 9314 C.H. 7	09-00034 -01-RS	MONROE	8	2

FEDERAL AID PROJECT  
CONTRACT 97443

- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 AND THE LATEST SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- EXCESS BITUMINOUS REMOVAL SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTIONS.
- THE THICKNESS OF THE BITUMINOUS MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS, DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING MONROE COUNTY (48) HOURS IN ADVANCE PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES OR WORK REQUIRING INSPECTION OR APPROVAL.
- ALL TRAFFIC CONTROL (INCLUDING, BUT NOT LIMITED TO WORK ZONE, TEMPORARY AND PERMANENT) SHALL BE FURNISHED, INSTALLED, MAINTAINED, RELOCATED AND/OR REMOVED IN ACCORDANCE WITH SECTION 701 OF THE LATEST EDITION OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- NO OVERNIGHT LANE CLOSURES SHALL BE ALLOWED.
- TRAFFIC CONTROL SIGNS SHALL BE 48" FLOURESCENT ORANGE
- ALL TEMPORARY PAVEMENT MARKINGS WILL BE PLACED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
- REMOVAL OF EXISTING AGGREGATE SHOULDER AT DRIVES FOR THE PURPOSE OF OBTAINING THE MINIMUM ASPHALT DEPTH (1") WILL NOT BE MEASURED, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR HOT-MIX ASPHALT REMOVAL - BUTT JOINT.
- ACCESS SHALL BE PROVIDED FROM PRIVATE ENTRANCES AT ALL LOCATIONS DURING ALL STAGES.
- APRONS OF DRIVES AND MAILBOX TURNOUTS PAVED WITH EXTENDABLE SCREED WIDENERS WILL BE CONSIDERED AN INTEGRAL PART OF MAINLINE PAVING AND WILL NOT BE MEASURED FOR PAYMENT AS INCIDENTAL HOT-MIX ASPHALT SURFACING.
- THE CONTRACTOR SHALL BE AWARE OF THE POSSIBILITY OF ON-GOING CONSTRUCTION ON LAKEVIEW DRIVE, CONTRACT NO. 97403, AND SHALL USE WHATEVER MEANS POSSIBLE TO COOPERATE PER ARTICLE 105.08 OF THE STANDARD SPECIFICATIONS.

FACTORS USED FOR QUANTITY CALCULATIONS ARE AS FOLLOWS:  
 ALL HOT-MIX ASPHALT - 112 LB/SQ YD PER 1" THICKNESS  
 AGGREGATE (PRIME COAT) - 3 LB/SQ YD  
 BITUMINOUS MATERIAL (PRIME COAT) OVER ASPHALT - 0.05 GAL/SQ YD  
 ALL AGGREGATE - 2.05 TONS/CU YD

SALVAGE: EXISTING GUARDRAIL: INCLUDING RAIL, POSTS, TERMINALS & HARDWARE.  
 MILLINGS  
 REFER TO SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION

## SUMMARY OF QUANTITY

CODE	ITEM	UNIT	QUANT.
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	43.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1405
40600300	AGGREGATE (PRIME COAT)	TON	41.1
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1092.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	969.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL- BUTT JOINT	SQ.YD.	98.0
40600990	TEMPORARY RAMP	SQ.YD.	68.0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1820.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	223.5
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ.YD.	1896.0
44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	SQ.YD.	26,121.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	920.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	58.0
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	3175.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	16.0
63200310	GUARDRAIL REMOVAL	FOOT	3917.0
67100100	MOBILIZATION	L SUM	1.0
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3190.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28853.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ.FT.	355.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28853.0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	49.0
* 78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	16.0

\* SPECIALTY ITEMS

LAKEVIEW DRIVE RESURFACING  
 GENERAL NOTES &  
 SUMMARY OF QUANTITIES  
 SEC 09-00034-01-RS  
 CITY OF WATERLOO  
 MONROE COUNTY, ILLINOIS