CONTRACT NO. 98823

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	24
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

* FAU 9481, FAS 2887 (IL 37)
** (12,12X),RS-3;12B-1,12B1-1
*** FRANKLIN AND WILLIAMSON

PAVEMENT

LOCATION STATION TO STATION	MATERIAL TRANSFER DEVICE TON	SUB-BASE GRANULAR MATERIAL TYPE A, 6" SQ YD	HOT-MIX BASE COURSE WIDENING, 9" SQ YD	POLYMERIZED BITUMINOUS MATERIALS PRIMECOAT GALLON	AGGREGATE PRIMECOAT TON	TEMPORARY PAVEMENT 9.5" SQ YD	LEVELING BINDER (MACHINE METHOD), N90 TON	HMA BINDER COURSE IL-19.0, N90 TON	POLY HMA SURFACE COURSE MIX "D", N90 TON	HMA SURFACE COURSE MIX "C", N90 TON	PCC PAVEMENT 10" (JOINTED) SQ YD	STRIP REFLECTIVE CRACK CONTROL FOOT	REMARKS
FRANKLIN COUNTY													
FAU 9481 (IL 37)													
STA 79+75 TO 80+71	36			74	0.6		17		36			288	
STA 80+71 TO 83+18	87			182	1.6		43		87			494	
STA 83+18 TO 87+00	86			184	1.5		43		86			382	
STA 87+00 TO 90+71	84			174	1.5		42		84			371	
STA 90+71 TO 91+29											155		
STA 91+29 TO 94+19.21 BK	66			136	1.1		33		66				GRADE RAISE AT POND CREEK
STA 366+03.65 AH TO 372+40	143			306	2.5		71		143				
STA 90+63							3						TEMP TRANSITIONS AT BOX CULVERT
STA 91+37							3						TEMP TRANSITIONS AT BOX CULVERT
STA 372+34							6						NEEDED DURING BRIDGE STAGING
TOTAL FROM SHOULDER SCHEDULE				1424				1428					
LOCATION TOTAL	502	0	0	2480	8.8	0	261	1428	502	0	155	1535	
FAS 2887 (IL 37)													
STA 374+60 TO 377+00	50			106	0.9		25		50			240	
STA 377+00 TO 382+93.50 BK	123			262	2.2		62		123			1782	
STA 382+98.60 AH TO 403+20	417			890	7.4		209		417			6063	
STA 403+20 TO 407+77	145			310	2.6		73		145			1371	
STA 407+77 TO 457+12	1019			2172	18.1		511		1019			14805	
STA 374+66							6						SEE DETAIL FOR TRANSITION AT BRIDGE
RT STA 9+05 COUNTRY CLUB RD		166	128	42	0.7					39			COUNTRY CLUB ROAD
TOTAL FROM SHOULDER SCHEDULE				3985				322					
LOCATION TOTAL	1754	166	128	7767	31.9	0	886	322	1754	39	0	24261	BINDER INCLUDED W/BRIDGE QTY
FRANKLIN COUNTY PROJECT TOTALS	2256	166	128	10247	40.7	0	1147	1750	2256	39	155	25796	
WILLIAMSON COUNTY													
FAS 2887 (IL 37)													
STA 457+12 TO 477+33.40 BK	417			890	7.4		209		417			6066	
STA 477+36.79 AH TO 525+72	999			2128	17.7		501		999			14505	
STA 525+72 TO 529+50	105			174	1.4		155		105			1134	
STA 529+50 TO 537+90	232			632				1439	232				GRADE CUT REGION
STA 537+90 TO 551+50	376			616	5.1			914	376			4080	GRADE RAISE REGION
STA 551+50 TO 560+90	260			704				1602	260				GRADE CUT REGION
STA 560+90 TO 564+12	89			148	1.2		90		89			966	
STA 564+12 TO 577+41	275			584	4.9		138		275			3987	
STA 1+00 TO 13+82.30				745		3127							DETOUR RD NO. 1
STA 1+00 TO 14+57.34				798		3217							DETOUR RD NO. 2
TOTAL FROM SHOULDER SCHEDULE				5618									
LOCATION TOTAL	2753	0	0	13037	37.7	6344	1093	3955	2753	0	0	30738	
WILLIAMSON COUNTY PROJECT TOTALS	2753	0	0	13037	37.7	6344	1093	3955	2753	0	0	30738	
PROJECT TOTAL	5009	166	128	23284	78.4	6344	2240	5705	5009	39	155	56534	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ. NO SCALE

DATE

DRAWN BY CNH

CHECKED BY

PLOT DATE = 3/2/2010
FILE NAME = c:\pwworking\PWIDOT\WEEMSSF\dms43550\cf924020 3sv.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = weemsbf