

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	25
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	

\* FAU 9481, FAS 2887 (IL 37)  
 \*\* (12,12X),RS-3;12B-1,12B1-1  
 \*\*\* FRANKLIN AND WILLIAMSON

### SHOULDERS

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE SHOULDERS, TYPE A, 8"	HOT-MIX ASPHALT SHOULDERS, 8"	HOT-MIX ASPHALT SHOULDERS	HMA BINDER COURSE IL 19.0, N90	SUB-BASE GRANULAR MATERIAL, TYPE C	REMARKS
	GALLON	SQ YD	SQ YD	TON	TON	TON	
<b>FRANKLIN COUNTY</b>							
<b>FAU 9481 (IL 37)</b>							
STA 79+75 TO 80+71							
STA 80+71 TO 83+18		21	181				INCLUDES 2 ENTRANCES
STA 83+18 TO 87+00	181	153	527				INCLUDES 2 ENTRANCES
STA 87+00 TO 90+71	335	162		35	350		BINDER REQUIRED FOR STRUCT REPLACE SEE TYPICALS
STA 90+71 TO 91+29				8	83		
STA 91+29 TO 94+19.21 BK	282	126		174	314		BINDER REQUIRED FOR STRUCT REPLACE; MAX. 8" FINAL HMA SHOULDER
STA 366+03.65 AH TO 372+40	626	284		442	620		
RT STA 89+18 TO 90+71						61	STAGE 2 SHOULDER WIDTH CORRECTION
STA 366+73 TO 368+64							
TOTAL FROM PAVEMENT SCHEDULE	1056					0	
LOCATION TOTAL	2480	746	708	659	1428		
<b>FAS 2887 (IL 37)</b>							
STA 374+60 TO 377+00	219	78		70	249		BINDER REQUIRED FOR STRUCT REPLACE
STA 377+00 TO 382+93.50 BK	282	200	856				INCLUDES 7 ENTRANCES
STA 382+98.60 AH TO 403+20	959	738	2864				INCLUDES 22 ENTRANCES
STA 403+20 TO 407+77	184	85	477				INCLUDES 3 ENTRANCES
STA 407+77 TO 457+12	2341	1976	6715				INCLUDES 34 ENTRANCES
RT STA 374+66 TO 376+25						73	STAGE 2 SHOULDER WIDTH CORRECTION
TOTAL FROM PAVEMENT SCHEDULE	3782					322	
LOCATION TOTAL	7767	3077	10912	70	322		
<b>FRANKLIN COUNTY PROJECT TOTALS</b>							
	10247	3823	11620	729	1750	0	
<b>WILLIAMSON COUNTY</b>							
<b>FAS 2887 (IL 37)</b>							
STA 457+12 TO 477+33.40 BK	959	800	2783				INCLUDES 15 ENTRANCES
STA 477+36.79 AH TO 525+72	2293	1884	6705				INCLUDES 41 ENTRANCES
STA 525+72 TO 529+50	179	140	532				INCLUDES 6 ENTRANCES
STA 529+50 TO 537+90	358	344	1150			312	INCLUDES 5 ENTRANCES
STA 537+90 TO 551+50	645	536	1884				INCLUDES 12 ENTRANCES
STA 551+50 TO 560+90	401	364	1308			347	INCLUDES 9 ENTRANCES
STA 560+90 TO 564+12	153	138	436				INCLUDES 1 ENTRANCE
STA 564+12 TO 577+41	630	543	1821				INCLUDES 11 ENTRANCES
TOTAL FROM PAVEMENT SCHEDULE	7419				3955		
LOCATION TOTAL	13037	4749	16619	0	3955	659	
<b>WILLIAMSON COUNTY PROJECT TOTALS</b>							
	13037	4749	16619	0	3955	659	
<b>PROJECT TOTAL</b>							
	23284	8572	28239	729	5705	659	

PLOT DATE = 3/2/2010  
 FILE NAME = c:\p\work\p\1001\WEEK5BF\dms43659.dgn  
 PLOT SCALE = 50:2000 / IN.  
 USER NAME = wemast

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE

SCALE: VERT. NO SCALE  
 HORIZ. NO SCALE  
 DATE

DRAWN BY CNH  
 CHECKED BY