

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GUARDRAIL

* FAU 9481, FAS 2887 (IL 37)
 *(12,12X),RS-3;12B-1,12B1-1
 *** FRANKLIN AND WILLIAMSON

LOCATION STATION TO STATION	SPBGR TYPE A 6 FT POST	TEMP SPBGR TYPE A	TRAFFIC BARRIER TERMINAL TYPE 6	TEMP TRAF BAR TERMINAL TYPE 10	TRAF BAR TERM TY 1 SPL TAN	TEMP TRAFF BAR TERM T 1 SPL TAN	SPBGR SHORT RADIUS	GUARDRAIL REMOVAL	GUARD RAIL MARKERS, TYPE B	TERMINAL MARKER- DIRECT APPLIED	REMARKS
	FOOT		EACH	EACH	EACH	EACH	FOOT	FOOT	EACH	EACH	
FRANKLIN COUNTY											
FAU 9481 (IL 37)											
SN 028-2003(E)											
RT STA 89+37.5 TO 92+62.5 (STAGE 1)		200		2		2		122	5	2	
RT STA 89+75 TO 91+62.5 (STAGE 2)	62.5				2				4	2	
RT STA 89+37.5 TO 92+62.5 (STAGE 2)								300			
LT STA 90+37.5 TO 91+68.5 (STAGE 1)	41.5				1		22	122	3	2	REMOVE STAGE 1 FOR STAGE 2 CONSTRUCTION FIELD CUT TO CONNECT TO SHORT RADIUS
LOCATION TOTAL	104.0	200	0	2	3	2	22	544	12	6	
FAS 2887 (IL 37)											
SN 028-0035(E)											
RT STA 370+99.5 TO 372+12 (STAGE 1)		62.5				1		25	3	1	REMOVE EXISTING TURN DOWN FOR TEMPORARY RAIL
RT STA 371+00 TO 375+96 (STAGE 2)								496			REMOVE STAGE 1 FOR STAGE 2 CONSTRUCTION (INCLUDES BRIDGE RAIL OR THRIE BEAM REMOVAL)
RT STA 371+76 TO 372+70 (STAGE 2)			1			1			2	1	
LT STA 371+76 TO 372+70 (STAGE 1)			1			1			3	1	
LT STA 371+88.75 TO 375+11 (STAGE 1)								322			REMOVE FOR BRIDGE CONSTRUCTION STAGE 1 (INCLUDES BRIDGE RAIL OR THRIE BEAM REMOVAL)
SN 028-0035(E)		62.5				1		25	3	1	REMOVE EXISTING TURN DOWN FOR TEMPORARY RAIL
RT STA 374+83 TO 375+95.5 (STAGE 1)			1			1			2	1	
RT STA 374+30 TO 375+24 (STAGE 2)			1			1			2	1	
LT STA 374+30 TO 375+24 (STAGE 1)			1			1			2	1	
LOCATION TOTAL	0.0	125	4	0	4	2	0	868	15	6	
FRANKLIN COUNTY PROJECT TOTALS	104.0	325	4	2	7	4	22	1412	27	12	
PROJECT TOTAL	104.0	325	4	2	7	4	22	1412	27	12	

TEMPORARY TRAFFIC BARRIERS

LOCATION STATION TO STATION	PORTABLE TEMPORARY BARRIER SYSTEM	IMPACT ATTEN, TEMPORARY (NON-REDIRECT) TEST LEVEL 3	IMPACT ATTEN, RELOCATE (NON-REDIRECT) TEST LEVEL 3	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY CONCRETE BARRIER	REMARKS
	FOOT	EACH	EACH	FOOT	FOOT	
FRANKLIN COUNTY						
FAU 9481 (IL 37)						
BOX CULVERT CONSTRUCTION						
STA 89+19 TO 92+81.5				750		STAGE 1 & 2 BOX CULVERT TOTAL SEE PLAN
STA 89+19			1			RELOCATE FROM BRIDGE TO STAGE 1
STA 89+19			1			RELOCATE FROM STAGE 1 TO STAGE 2
STA 92+81.5			1			RELOCATE FROM BRIDGE TO STAGE 1
STA 92+81.5			1			RELOCATE FROM STAGE 1 TO STAGE 2
LOCATION TOTAL	0	0	4	750	0	
BRIDGE CONSTRUCTION						
STA 371+49 TO 375+49					400	STAGE 1 BRIDGE
STA 371+49		1				STAGE 1 BRIDGE
STA 375+49		1				STAGE 1 BRIDGE
STA 370+86 TO 376+11				400	125	STAGE 2 BRIDGE
STA 370+86			1			STAGE 2 BRIDGE
STA 376+11			1			STAGE 2 BRIDGE
LOCATION TOTAL	0	2	2	400	525	
FRANKLIN COUNTY PROJECT TOTALS	0	2	6	1150	525	
WILLIAMSON COUNTY						
FAS 2887 (IL 37)						
DETOUR ROAD NO. 1						
RT STA 3+50 TO 11+30	780					
LT STA 10+76.5 TO 12+78	202					
DETOUR ROAD NO. 2						
LT STA 3+50 TO 12+14.5	865					
LOCATION TOTAL	1846	0	0	0	0	
WILLIAMSON COUNTY PROJECT TOTALS	1846	0	0	0	0	
PROJECT TOTAL	1846	2	6	1150	525	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. NO SCALE
 HORIZ. DATE
 DRAWN BY CNH
 CHECKED BY