

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	38

STA.	TO STA.
FED. ROAD DIST. NO. -	ILLINOIS FED. AID PROJECT

* FAU 9481, FAS 2887 (IL 37)
 ** (12,12X),RS-3;12B-1,12B1-1
 *** FRANKLIN AND WILLIAMSON

EROSION CONTROL

LOCATION STATION TO STATION	PROPOSED DITCH WIDTH	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	REMARKS
	FEET	SQ YD	SQ YD	FOOT	FOOT	EACH	
FRANKLIN COUNTY							
FAU 9481 (IL 37)							
LT STA 90+60 TO 90+90				18		40	
LT STA 91+15 TO 91+45				18		40	
LT STA 92+00 TO 94+19		244				219	
LT STA 366+04 TO 370+00		440				397	
LT STA 371+75 TO 372+40						65	
LT STA 372+40 TO 372+70				79		120	
RT STA 79+75							
RT STA 90+60 TO 90+90				18		40	
RT STA 91+15 TO 91+45				18		40	
RT STA 91+45 TO 94+19		305				274	
RT STA 366+04 TO 372+40		707				639	
RT STA 372+40 TO 372+70				79		120	
LOCATION TOTAL		1696	230	10	1994	1	
FAS 2887 (IL 37)							
LT STA 374+30 TO 374+60			79			120	
LT STA 374+55 TO 376+20		183				330	
LT STA 376+20 TO 377+48	12	171					
LT STA 378+30							1 INLET
LT STA 378+99							1 INLET
LT STA 379+47 TO 380+55	12	144		10	108		1 INLET
LT STA 381+33							1 INLET
LT STA 382+08 TO 382+97	12	119		10			
LT STA 383+56 TO 384+69	12	151		10			
LT STA 385+08 TO 386+46	12	184		10			
LT STA 386+77 TO 388+00	12	164		10	123		
LT STA 388+00 TO 389+49	12	199		10			
LT STA 389+98							1 INLET
LT STA 391+00							1 INLET
LT STA 392+38 TO 393+35	12	129		10			
LT STA 393+62 TO 394+72	12	147		10			
LT STA 395+02 TO 396+43	12	188		20			
LT STA 396+80							1 INLET
LT STA 397+17 TO 399+40	8	198		30			
LT STA 399+99							1
LT STA 400+46 TO 403+45	8	266		50			
LT STA 403+90 TO 406+33	8	216		40			
LT STA 406+73 TO 407+35	8	55		10			
LT STA 407+54 TO 410+27	8	243		40			
LT STA 411+15							1 INLET
LT STA 411+54 TO 412+64	8	98		10			
LT STA 412+91							1 INLET
LT STA 413+18 TO 413+52	8	30					
LT STA 413+77 TO 415+25	4	66		10			
LT STA 415+51 TO 417+71	4	98		30			
LT STA 417+95 TO 418+66	8	63		10			
LT STA 418+98 TO 420+10	8	100		10			
LT STA 420+97 TO 422+10	8	100		10			
LT STA 422+41 TO 423+48	8	95		10			
LT STA 424+76 TO 425+37	8	54					
LT STA 425+66 TO 426+46	8	71		10			1
LT STA 427+22 TO 428+57	4	60		20			
LT STA 429+02 TO 430+85	8	163		20			
LT STA 431+15 TO 433+40	4	100		20			
LT STA 433+78 TO 434+35	8	51					
LT STA 434+65 TO 436+00	4	60		10			
LT STA 436+00 TO 436+37	8		33	20			1
LT STA 437+85 TO 438+66	8	72		10			
LT STA 438+98 TO 441+47	8	221		40			
LT STA 441+71 TO 445+08	8	300		40			
LT STA 445+41 TO 447+04	8	145		10			
LT STA 447+45 TO 449+25	8	160		20			
LT STA 449+63 TO 451+25	8	144		10			
LT STA 451+75 TO 454+78	8	269		20			

SHEET 1 OF 4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. NO SCALE
 HORIZ. NO SCALE
 DATE

DRAWN BY CNH
 CHECKED BY