

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	***	304	43

STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

\* FAU 9481, FAS 2887 (IL 37)  
 \*\* (12,12X),RS-3;12B-1,12B1-1  
 \*\*\* FRANKLIN AND WILLIAMSON

### SEEDING

LOCATION STATION TO STATION	SEEDING, CLASS 2 MODIFIED ACRE	SEEDING, CLASS 7 ACRE	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHOROUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	AGRICULTURAL GROUND LIMESTONE TON	MULCH, METHOD 2 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	REMARKS
<b>FRANKLIN COUNTY</b>									
FAU 9481 (IL 37)									
STA 79+75 TO 372+40	1.3	1.3	210.0	158.0	158.0	2.6	2.6	130.0	
LOCATION TOTAL	1.3	1.3	210.0	158.0	158.0	2.6	2.6	130.0	
<b>FAS 2887 (IL 37)</b>									
STA 374+60 TO 457+12	9.6	9.6	1,530.0	1,147.0	1,147.0	19.1	19.1	960.0	
LOCATION TOTAL	9.6	9.6	1,530.0	1,147.0	1,147.0	19.1	19.1	960.0	
<b>FRANKLIN COUNTY PROJECT TOTALS</b>	<b>10.9</b>	<b>10.9</b>	<b>1,740.0</b>	<b>1,305.0</b>	<b>1,305.0</b>	<b>21.7</b>	<b>21.7</b>	<b>1,090.0</b>	
<b>WILLIAMSON COUNTY</b>									
FAS 2887 (IL 37)									
STA 457+12 TO 525+00	8.2	8.2	1,316.0	987.0	987.0	16.4	16.4	820.0	
<b>STAGE 1</b>									
RT STA 525+00 TO 540+00									NO SEEDING STAGE 1 RT
LT STA 525+00 TO 540+00		1.3	52.0				1.3	130.0	TEMPORARY SEEDING
<b>STAGE 2</b>									
RT STA 525+00 TO 540+00	1.3	1.3	208.0	156.0	156.0	2.6	2.6	130.0	
LT STA 525+00 TO 540+00		0.2	6.0				0.2	20.0	TEMPORARY SEEDING
<b>STAGE 3</b>									
RT STA 525+00 TO 540+00	0.1	0.1	14.0	10.0	10.0	0.2	0.2	10.0	
LT STA 525+00 TO 540+00	1.7	1.7	277.0	208.0	208.0	3.5	3.5	170.0	
STA 540+00 TO 543+48	0.5	0.5	88.0	66.0	66.0	1.1	1.1	50.0	
<b>STAGE 1</b>									
RT STA 543+48 TO 569+00		2.1	83.0				2.1	210.0	TEMPORARY SEEDING
LT STA 543+48 TO 569+00									NO SEEDING STAGE 1 LT
<b>STAGE 2</b>									
RT STA 543+48 TO 569+00		0.2	6.0				0.2	20.0	TEMPORARY SEEDING
LT STA 543+48 TO 569+00	2.2	2.2	352.0	264.0	264.0	4.4	4.4	220.0	
<b>STAGE 3</b>									
RT STA 543+48 TO 569+00	2.3	2.3	372.0	279.0	279.0	4.6	4.6	230.0	
LT STA 543+48 TO 569+00	0.2	0.2	28.0	21.0	21.0	0.4	0.4	20.0	
STA 569+00 TO 577+41	1.0	1.0	156.0	117.0	117.0	1.9	1.9	100.0	
LOCATION TOTAL	17.5	21.3	2,958.0	2,108.0	2,108.0	35.1	38.9	2,130.0	
<b>WILLIAMSON COUNTY PROJECT TOTALS</b>	<b>17.5</b>	<b>21.3</b>	<b>2,958.0</b>	<b>2,108.0</b>	<b>2,108.0</b>	<b>35.1</b>	<b>38.9</b>	<b>2,130.0</b>	
<b>PROJECT TOTAL</b>	<b>28.4</b>	<b>32.2</b>	<b>4,698.0</b>	<b>3,413.0</b>	<b>3,413.0</b>	<b>56.8</b>	<b>60.6</b>	<b>3,220.0</b>	

PLOT DATE = 12/7/2009  
 FILE NAME = S:\pwork\1\1001\HEADN\dm53559\af984003b.dgn  
 USER NAME = headn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE

SCALE: VERT. NO SCALE  
 HORIZ. DATE

DRAWN BY CNH  
 CHECKED BY