CONTRACT NO. 98823

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	304	70
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAU 9481, FAS 2887 (IL 37)
** (12,12X),RS-3;12B-1,12B1-1
*** FRANKLIN AND WILLIAMSON

PLAN
SURVEYED
PLOTTED
DRAWN
CHECKED
NOTE BOOK
NO.
BY
DATE
ALIGNMENT CHECKED
PT. OF BEG. CHECKED
BEAR. NO. TIES
BEAR. TIES
PROP. TIES
BENCH MARKS
NOTE BOOK
NO.

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
BEAR. NO. TIES
BEAR. TIES
PROP. TIES
BENCH MARKS (OTHER THAN BEG. & END)
NOTE BOOK
NO.
BY
DATE

PLOT DATE = 12/7/2009
FILE NAME = c:\pw_work\PWIDOT\HEADON\dms436581\d9249036p6.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = headon

℄ IL 37

STA. 10+00 COUNTY LINE ROAD =
STA. 457+12.74 IL 37

50' R. (TYP.)

POT Sta 8+61.24

+37.4

18'

℄ COUNTY LINE ROAD

REMOVE EXISTING OIL AND CHIP SURFACE AS EARTH EXCAVATION

10+00

NOTES: FOR PROPOSED DRAINAGE NOTES SEE THE PLAN PROFILE SHEETS.
FOR EROSION CONTROL NOTES SEE EROSION CONTROL SHEETS.

N

9

10' 0 5 ' 10'

2' 6' 22' 6' 2'

30.00' V.C.

℄ COUNTY LINE ROAD
EXISTING OIL AND CHIP SURFACE

+50.00 EL. 457.16

+80.00 EL. 457.06

EDGE OF PAVEMENT OF IL 37
STA. 9+89.0 ELEV. 457.19
SIDE ROAD
IMPROVEMENT ENDS

-2.17% +1.50% +1.50%

STA. 9+37.4
ELEV. 457.43
SIDE ROAD
IMPROVEMENT
BEGINS

VPI STA. 9+65.00
ELEVATION 456.83

VPI STA. 9+81.00
ELEVATION 457.07

INCIDENTAL HOT-MIX ASPHALT SURFACING 3"
AGGREGATE BASE COURSE, TYPE B 8"

458
457
456
455
454
453

457.81 457.73 457.66 457.58 457.54 457.52 457.49 457.44 457.41 457.37 457.39 457.26 457.35 457.16 457.32 457.06 457.28 457.00 457.24 456.97 457.21 456.97 457.18 457.00 457.15 457.06 457.13

+90 9+00 +10 +20 +30 +40 +50 +60 +70 +80 +90 10+00

COUNTY LINE ROAD