

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 924	09-00062-00-RS	JOHNSON	10	3
PROJECT NO. ARA-RS-924 (124)			CONTRACT NO. 99372	

RESURFACING SCHEDULE

Location Station to Station	Length Feet	Prime Coat		Leveling Binder (MM)		Hot-Mix Asphalt Binder Course Tons	Hot-Mix Asphalt Surface Course Tons
		Bituminous Materials Gallons	Aggregate Tons	Full Lift Tons	Crown/SE Correction Tons		
		EASTBOUND (RIGHT) LANE					
0+60 to 5+12	452.00	58.6	0.9	24.6	20.4		41.0
5+12 to 11+31	619.00	70.8	1.0	29.8	12.7		49.5
11+31 to 18+82	751.00	86.0	1.3	36.1	73.4		60.1
18+82 to 23+23	441.00	50.5	0.8	21.2	19.8		35.3
23+23 to 24+35	112.00	12.8	0.2	5.4	4.4		8.9
24+35 to 26+48	213.00	24.3	0.3	10.6		36.7	17.1
26+48 to 30+00	352.00	40.3	0.7	16.9	34.3	0.3	28.2
30+00 to 34+12	412.00	47.2	0.7	19.8	19.4		32.9
34+12 to 36+49	237.00	27.1	0.4	11.4	5.0	18.0	19.0
36+49 to 45+60	911.00	104.3	1.5	43.8	21.8		72.9
45+60 to 49+33	373.00	42.7	0.7	17.9	36.6		29.8
49+33 to 60+52	1119.00	128.0	1.9	53.8	56.6	4.0	89.6
60+52 to 65+35	483.00	55.3	0.8	23.2	15.6	31.6	38.6
65+35 to 66+69	134.00	15.3	0.2	6.7		2.4	16.3
66+69 to 69+26	257.00	29.4	0.5	12.4	3.4		27.2
69+26 to 71+89	263.00	30.1	0.4	12.6	5.9	22.3	21.1
71+89 to 89+22	1733.00	198.4	3.0	83.3	32.6		138.7
89+22 to 94+44	522.00	59.7	0.9	25.1	31.0	17.3	41.7
94+44 to 105+60	1116.00	127.7	1.9	53.6	26.4		89.3
Subtotals for EastBound (Right) Lane		1208.5	18.1	508.2	419.3	132.6	857.2
WESTBOUND (LEFT) LANE							
0+60 to 5+12	452.00	58.6	0.9	24.6	17.9	8.3	41.0
5+12 to 11+31	619.00	70.8	1.0	29.8	5.7	77.3	49.5
11+31 to 18+82	751.00	86.0	1.3	36.1	26.4		60.1
18+82 to 23+23	441.00	50.5	0.8	21.2	8.5	38.3	35.3
23+23 to 24+35	112.00	12.8	0.2	5.4	5.5		8.9
24+35 to 26+48	213.00	24.3	0.3	10.2	10.9		17.1
26+48 to 30+00	352.00	40.3	0.7	16.9	8.9	63.8	28.2
30+00 to 34+12	412.00	47.2	0.7	19.8	26.3		32.9
34+12 to 36+49	237.00	27.1	0.4	11.4	14.1		19.0
36+49 to 45+60	911.00	104.3	1.5	43.8	46.9		72.9
45+60 to 49+33	373.00	42.7	0.7	17.9	3.1	131.9	29.8
49+33 to 60+52	1119.00	128.0	1.9	53.8	47.4		89.6
60+52 to 65+35	483.00	55.3	0.8	23.2	12.8		38.6
65+35 to 66+69	134.00	15.3	0.2	6.5			16.3
66+69 to 69+26	257.00	29.4	0.5	12.4	19.8		27.2
69+26 to 71+89	263.00	30.1	0.4	12.6	10.0		21.1
71+89 to 89+22	1733.00	198.4	3.0	83.3	79.4		138.7
89+22 to 94+44	522.00	59.7	0.9	25.1	20.7	18.4	41.7
94+44 to 105+60	1116.00	127.7	1.9	53.6	51.8		89.3
Subtotals for WestBound (Left) Lane		1208.5	18.1	507.6	416.1	338.0	857.2
TOTALS		2417.0	36.2	1015.8	835.4	470.6	1714.4

**LOCATIONS FOR
HOT-MIX ASPHALT BINDER COURSE**

Location	Tons
EASTBOUND (RIGHT) LANE	
Sta. 24+40 - Sta. 26+50	37.0
Sta. 34+75 - Sta. 36+25	18.0
Sta. 60+20 - Sta. 61+70	19.0
Sta. 64+30 - Sta. 65+50	19.0
Sta. 69+65 - Sta. 71+40	22.3
Sta. 89+40 - Sta. 90+50	17.3
WESTBOUND (LEFT) LANE	
Sta. 3+65 - Sta. 4+40	8.3
Sta. 5+30 - Sta. 10+60	77.3
Sta. 19+50 - Sta. 22+70	38.3
Sta. 27+25 - Sta. 29+40	63.8
Sta. 45+60 - Sta. 48+90	131.9
Sta. 91+10 - Sta. 92+30	18.4
TOTAL	470.6

NOTE: Locations and quantities are estimated and should be verified and adjusted in the field as directed by the Engineer.

NOTE: Quantities shown do not include materials for entrances, side roads, shoulder paving and mailbox turnouts.