

SUMMARY OF QUANTITIES

SEQ NO	ITEM NO	DESCRIPTION	UNIT	QUANTITY (F/S/L)	RECORD QUANTITY	QUANTITY (L)	RECORD QUANTITY
1	AR108108	1/C #8 KV CABLE	L.F.	13,600.00			
2	AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	7,690.00			
3	AR108812	12 PAIR CONTROL CABLE	L.F.	1,400.00			
4	AR109210	VAULT MODIFICATIONS	L.S.	1.00			
5	AR110212	2" STEEL DUCT, DIRECT BURY	L.F.	6,430.00			
6	AR110213	3" STEEL DUCT, DIRECT BURY	L.F.	200.00			
7	AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	190.00			
8	AR110554	EXTEND 4-WAY DUCT	L.F.	280.00			
9	AR110610	ELECTRICAL HANDHOLE	EACH	1.00			
10	AR110714	ELECTRICAL MANHOLE, 4'	EACH	2.00			
11	AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	15.00			
12	AR125415	MITL-BASE MOUNTED	EACH	148.00			
13	AR125420	TAXIWAY LIGHT INPAVEMENT	EACH	60.00			
14	AR125441	TAXIWAY GUIDANCE SIGN 1 CHAR	EACH	2.00			
15	AR125442	TAXIWAY GUIDANCE SIGN 2 CHAR	EACH	5.00			
16	AR125443	TAXIWAY GUIDANCE SIGN 3 CHAR	EACH	2.00			
17	AR125444	TAXIWAY GUIDANCE SIGN 4 CHAR	EACH	2.00			
18	AR125445	TAXIWAY GUIDANCE SIGN 5 CHAR	EACH	3.00			
19	AR125446	TAXIWAY GUIDANCE SIGN 6 CHAR	EACH	2.00			
20	AR125525	HIRL, INPAVEMENT	EACH	3.00			
21	AR125565	SPLICE CAN	EACH	4.00			
22	AR125902	REMOVE BASE MOUNTED LIGHT	EACH	128.00			
23	AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	11.00			
24	AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.00			
25	AR150515	FIELD LABORATORY	L.S.	1.00			
26	AR150520	MOBILIZATION	LS	1.00			
27	AR150540	HAUL ROUTE	LS	1.00			
28	AR152410	UNCLASSIFIED EXCAVATION	C.Y.	10,910.00			
29	AR152442	OFFSITE BORROW EXCAVATION	C.Y.	1,600.00			
30	AR152540	SOIL STABILIZATION FABRIC	S.Y.	25,680.00			
31	AR156510	SILT FENCE	L.F.	3,284.00			
32	AR156512	BALES	EACH	100.00			
33	AR161601	TEMPORARY GATE	EACH	1.00			
34	AR208515	POROUS GRANULAR EMBANKMENT	C.Y.	2,130.00			
35	AR209606	CRUSHED AGG. BASE COURSE - 6"	S.Y.	7,000.00			
36	AR209612	CRUSHED AGG BASE COURSE - 12"	S.Y.	18,825.00			
37	AR401610	BITUMINOUS SURFACE COURSE	TON	5,600.00		200.00	
38	AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1.00			
39	AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	45,000.00		1,225.00	
40	AR403610	BITUMINOUS BASE COURSE	TON	10,850.00			
41	AR403630	BITUMINOUS BASE TEST SECTION	EACH	1.00			
42	AR501515	15" PCC PAVEMENT	S.Y.	20,350.00			
43	AR501530	PCC TEST BATCH	EACH	1.00			
44	AR602510	BITUMINOUS PRIME COAT	GAL.	8,925.00			
45	AR603510	BITUMINOUS TACK COAT	GAL.	11,865.00		175.00	
46	AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	24,950.00		500.00	
47	AR620525	PAVEMENT MARKING - BLACK BORDER	S.F.	24,390.00		500.00	
48	AR620900	PAVEMENT MARKING REMOVAL	S.F.	2,200.00			
49	AR701512	12" RCP, CLASS IV	L.F.	205.00			
50	AR701515	15" RCP, CLASS IV	L.F.	230.00			
51	AR701518	18" RCP, CLASS IV	L.F.	330.00			
52	AR701524	24" RCP, CLASS IV	L.F.	1,130.00			
53	AR701530	30" RCP, CLASS IV	L.F.	455.00			
54	AR701900	REMOVE PIPE	L.F.	3,030.00			
55	AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	4,200.00			
56	AR705900	REMOVE UNDEDRAIN	L.F.	1,700.00			
57	AR751412	TYPE B INLET	EACH	3.00			
58	AR751550	MANHOLE 5'	EACH	4.00			
59	AR751567	MANHOLE 7'	EACH	2.00			
60	AR751900	REMOVE INLET	EACH	6.00			
61	AR751903	REMOVE MANHOLE	EACH	14.00			
62	AR770704	SANITARY MANHOLE 4'	EACH	5.00			
63	AR800813	PREFORMED THERMOPLASTIC PVT MARKING	S.F.	5,785.00			
64	AR800815	PORTABLE LIGHTED RUNWAY CLOSURE MARKER	EACH	2.00			
65	AR800816	L-804 RGL ELEVATED, BASE MOUNTED	EACH	6.00			
66	AR800825	TRAFFIC CONTROL AND PROTECTION	L.S.	1.00			
67	AR800826	21" SANITART SEWER	L.F.	925.00			
68	AR800868	SOIL GUARD	S.Y.	48,270.00			
69	AR901510	SEEDING	ACRE	10.00			

RO018



Chicago Rockford
International
Airport



Rockford, Illinois

Greater Rockford
Airport Authority

AIP: 3-17-0088-XX
RFD-4008

Rehabilitate TXY J
and L

Revisions

Date	Description

0 1
THIS BAR IS EQUAL TO 1"
AT FULL SCALE (17 X 11).

DESIGN BY:	CMT- RFD
DRAWN BY:	CMT- RFD
CHECKED BY:	CMT- RFD
APPROVED BY:	CMT-RFD
DATE:	4-16-2010
JOB No:	09258-05-00

SUMMARY OF
QUANTITIES
(QTY1)

2

SUMMARY OF QUANTITIES
(QTY1)