

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
				0005
				HENDERSON
				80% FEDERAL 20% STATE
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2682	2682
48203012	HOT-MIX ASPHALT SHOULDERS, 3 3/4"	SQ YD	2071	2071
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQYD	1968	1968
50105220	PIPE CULVERT REMOVAL	FOOT	13	13
54262712	METAL FLARED END SECTIONS 12"	EACH	2	2
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	15	15
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2
63200310	GUARDRAIL REMOVAL	FOOT	50	50
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	4	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1

*= SPECIALTY ITEM

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5227 534	14RS-3,6RS-4,12RS-5	HENDERSON	111	5
			CONTRACT NO. 68503	
ILLINOIS FED. AID PROJECT				

REV. 5/27/21 REV. 4/26/21 REV. 4/1/21

MODEL: Proj\Illinois\Projects\68503\Notes, Summary of Quantities & Details.dgn
FILE NAME: S:\GENERAL\STDEP\MS_S040413\Lee Projects\68503\Notes, Summary of Quantities & Details.dgn

CLASS D PATCHES, TYPE 1, 5 INCH				
LOCATION				
STATION TO STATION	LENGTH	WIDTH	AREA (SQ FT)	AREA (SQ YD)
NB / SB CARMAN ROAD	(FOOT)	(FOOT)		
SB 336+00 TO 370+00	5	6	30	3.33
TOTAL				3.33

CLASS D PATCHES, TYPE 2, 5 INCH				
LOCATION				
STATION TO STATION	LENGTH	WIDTH	AREA (SQ FT)	AREA (SQ YD)
NB / SB IL 96	(FOOT)	(FOOT)		
NB 292+00 TO 300+00	20	6	120	13.33
NB 292+00 TO 300+00	20	6	120	13.33
NB 300+00 TO 308+00	20	6	120	13.33
CARMAN RD				
SB 450+00 TO 456+00	10	6	60	6.67
SB 450+00 TO 456+00	10	6	60	6.67
NB 415+00 TO 450+00	20	6	120	13.33
TOTAL				66.67

CLASS D PATCHES, TYPE 3, 5 INCH				
LOCATION				
STATION TO STATION	LENGTH	WIDTH	AREA (SQ FT)	AREA (SQ YD)
NB / SB CARMAN RD	(FOOT)	(FOOT)		
SB 282+00 TO 300+00	25	6	150	16.67
SB 282+00 TO 300+00	25	6	150	16.67
SB 318+00 TO 333+00	25	6	150	16.67
SB 333+00 TO 336+00	25	6	150	16.67
SB 456+00 TO 480+00	25	6	150	16.67
NB 497+00 TO 500+00	25	6	150	16.67
NB 459+00 TO 485+00	25	6	150	16.67
NB 394+00 TO 415+00	25	6	150	16.67
NB 384+00 TO 400+00	25	6	150	16.67
NB 384+00 TO 400+00	25	6	150	16.67
NB 384+00 TO 400+00	25	6	150	16.67
NB 254+00 TO 265+00	25	6	150	16.67
TOTAL				200.00

CLASS D PATCHES, TYPE 4, 5 INCH				
LOCATION				
STATION TO STATION	LENGTH	WIDTH	AREA (SQ FT)	AREA (SQ YD)
NB / SB	IL 96			
NB+SB 291+74	50	12	600	66.67
NB 292+00 TO 300+00	200	6	1200	133.33
NB 292+00 TO 300+00	40	6	240	26.67
NB 308+00 TO 315+00	250	6	1500	166.67
CARMAN ROAD				
SB 265+00 TO 282+00	200	6	1200	133.33
SB 265+00 TO 282+00	150	6	900	100.00
SB 300+00 TO 318+00	50	6	300	33.33
SB 384+00 TO 394+00	50	6	300	33.33
SB 384+00 TO 394+00	50	6	300	33.33
SB 394+00 TO 415+00	150	6	900	100.00
SB 394+00 TO 415+00	50	6	300	33.33
SB 415+00 TO 440+00	150	6	900	100.00
SB 415+0 TO 440+00	150	6	900	100.00
SB 415+00 TO 440+00	600	6	3600	400.00
SB 415+00 TO 440+00	50	6	300	33.33
SB 415+00 TO 440+00	50	6	300	33.33
SB 440+00 TO 450+00	150	6	900	100.00
SB 440+00 TO 450+00	75	6	450	50.00
NB+SB 500+00 TO 503+00	50	12	600	66.67
NB 497+00 TO 500+00	50	6	300	33.33
NB+SB 496+63	25	12	300	33.33
NB+SB 495+56	25	12	300	33.33
NB 415+00 TO 450+00	250	6	1500	166.67
NB 415+00 TO 450+00	100	6	600	66.67
NB 415+00 TO 450+00	50	6	300	33.33
NB+SB 415+00 TO 450+00	100	12	1200	133.33
NB 415+00 TO 450+00	40	6	240	26.67
NB 415+00 TO 450+00	100	6	600	66.67
NB 415+00 TO 450+00	100	6	600	66.67
NB 394+00 TO 415+00	50	6	300	33.33
NB 384+00 TO 400+00	75	6	450	50.00
NB+SB 384+00 TO 400+00	100	12	1200	133.33
NB 336+00 TO 370+00	150	6	900	100.00
NB 336+00 TO 370+00	150	6	900	100.00
TOTAL				2820.00

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		
LOCATION	AREA	AREA
STATION TO STATION	(SQ FT)	(SQ YD)
IL ROUTE 96		
291+74 TO 292+14	1040	115.56
330+73.20 TO 331+13.20	1040	115.56
IL 96 - SIDEROADS		
N. BONFIELD ST	468.85	52.09
S. BONFIELD BLVD	635.46	70.61
BLOOMINGTON RD.	464.00	51.56
N. BENTON ST.	444.24	49.36
S. BENTON ST.	749.55	83.28
N. AVISTON ST.	742.09	82.45
S. AVISTON ST.	595.69	66.19
AUBURN ST.	627.9	69.77
FOURTH ST.	578.78	64.31
CARMAN ROAD		
254+42 TO 254+82	960	106.67
376+66.29 TO 377+14.79	1551.8	172.42
379+84.72 TO 380+33.70	1567.56	174.17
485+67.31 TO 486+15.70	1158.55	128.73
486+64.80 TO 487+13.35	1168.02	129.78
495+09.23 TO 495+56.77	1140.66	126.74
496+63.61 TO 497+11.01	1164.93	129.44
CARMAN ROAD- SIDEROADS		
W. 750 N	764.13	84.90
E. 750 N	1035.28	115.03
W. 650 N	302.99	33.67
E. 650 N	301.62	33.51
E. 655	216.43	24.05
W. 575 N	223.96	24.88
E. 575 N	818.84	90.98
ASHER ST.	326.54	36.28
RUSSELL ST.	576.96	64.11
FIRST ST.	349.7	38.86
TOTAL		2335

REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

REGULATED SUBSTANCES MONITORING	
LOCATION	CAL DAY
JOBSITE	4
TOTAL	4

TRAFFIC CONTROL & PROTECTION, STANDARD 701201	
LOCATION	EACH
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STANDARD 701336	
LOCATION	EACH
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL & PROTECTION, STANDARD 701306	
LOCATION	EACH
JOBSITE	1
TOTAL	1

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL DAY
JOBSITE	14
TOTAL	14

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOBSITE	5
TOTAL	5

CONSTRUCTION LAYOUT	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

RAILROAD PROTECTIVE LIABILITY INSURANCE	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

MODEL: Default
FILE: \\mnp\p\GEN\DR\A\T\T\DR\PL\US\04\01\100 Projects\68503\Schedule of Quantities.dgn

DESIGNED	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES	
SCALE: N.T.S.	SHEET 1 OF 10 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5227 534	14RS-3: 6RS-4: 12RS-5	HENDERSON	111	8
CONTRACT NO. 68503				
ILLINOIS FED. AID PROJECT				