

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	GENERAL LOCATION MAP
5	SUMMARY OF PATCHING SCHEDULE
6-8	PATCHING SCHEDULE
9	BUTT JOINT AND HMA TAPER DETAILS
10	FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAILS
11	FREEWAY SINGLE & MULTI-LANE WEAVE
12-13	MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS
14	FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES

STATE STANDARDS

<u>STANDARD NO.</u>	<u>DESCRIPTION</u>
000001-05	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS
701101-02	OFF-RD. OPERATIONS, MULTILANE
701400-03	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-05	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-05	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP
701426-03	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION
701446-01	TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
701901-01	TRAFFIC CONTROL DEVICES

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

MIXTURE TYPE	AC TYPE	AIR VOIDS (%)
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 (IL 9.5MM), 2"	PG 64-22	4% @ 90 GYR

THE UNIT WEIGHT USED TO CALCULATE ALL HOT-MIX ASPHALT SURFACE MIXTURE QUANTITIES IS 112 LBS/SY/IN.

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "C.U.A.N." (CHICAGO UTILITY ALERT NETWORK) AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE (OR TOLLWAY) PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT (OR ISTHA).

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISABILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

ANY PAVEMENT MARKINGS AND RAISED REFLECTIVE PAVEMENT MARKERS OBLITERATED BY MILLING AND RESURFACING OPERATIONS ON SIDE STREETS AND ENTRANCES SHALL BE REPLACED AND PAID FOR IN KIND.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4155 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT MS. PATRICE HARRIS, AREA TRAFFIC FIELD ENGINEER AT (708) 597-9800 MINIMUM OF TWO (2) WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE EXISTING ROADWAY TYPICAL SECTION FOR HOT-MIX ASPHALT SURFACES IS ASSUMED TO HAVE A 3 INCH HOT-MIX ASPHALT OVERLAY ON TOP OF A TEN INCH CONCRETE BASE. THE EXISTING ROADWAY TYPICAL SECTION FOR CONCRETE SURFACES IS ASSUMED TO BE 10 INCHES OF FULL DEPTH PORTLAND CEMENT CONCRETE PAVEMENT.

ALL PAVEMENT PATCHES ON HOT-MIX ASPHALT SURFACES SHOWN IN THE PLANS ARE TO BE TWO (2) INCH MILL AND RESURFACE ONLY. THE MINIMUM WIDTH FOR MILLING AND PATCHING SHALL BE TWO (2) FEET. ALL PAVEMENT PATCHES ON CONCRETE SURFACES ARE TO BE 10 INCH CLASS D PATCHES.

THE COST OF ANY PARTIAL OR FULL DEPTH PATCHING REQUIRED AFTER THE REMOVAL OF THE EXISTING 2 INCH HOT-MIX ASPHALT SURFACE SHALL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.

ALL LANE LINES, EDGE LINES, AND GORE MARKINGS ARE TO BE RESTRIPE ON I-55 (STEVENSON EXPRESSWAY) WITHIN THE PROJECT LIMITS (I-294 TO KEDZIE AVE.).

ALL LANES LINES ARE TO BE THERMOPLASTIC (OF THE EXTRUDED KIND). ALL EDGE LINES AND GORE MARKINGS ARE TO BE HOT SPRAY THERMOPLASTIC. EXISTING POLYUREA LANE LINE MARKINGS ARE TO BE REMOVED PRIOR TO PLACEMENT OF NEW THRMOPLASTIC PAVEMENT MARKINGS.

Rev. 5-27-09

FILE NAME =	USER NAME = WILGREENDP	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\PW1007\WILGREENDP\01251099\01sign.dgn	DRAWN -	REVISED -	55			2007-0181	COOK	14	2	
PLOT SCALE = 100.0000 / IN.	CHECKED -	REVISED -	CONTRACT NO. 60C73							
PLOT DATE = 3/19/2009	DATE -	REVISED -	FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT							
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5															
40600300	AGGREGATE (PRIME COAT)	TON	22	22															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	33	33															
40600895	CONSTRUCTING TEST STRIP	EACH	1	1															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	545	545															
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1219	1219															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	10881	10881															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	11701	11701															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4876	4876															
*78000200	THERMOPLASTIC PAVEMENT MARKING LINE 4"	FOOT	25893	25893															
*78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID LINE 5"	FOOT	11701	11701															
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1171	1171															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1171	1171															
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1															
*78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	59,600	59,600															
*78000815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	238,400	238,400															
*78000845	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 8 INCH	FOOT	30,500	30,500															
*78000855	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 12 INCH	FOOT	5,200	5,200															
78300100	PAVEMENT MARKING REMOVAL	SQ FT	12,417	12,417															

* SPECIALTY ITEM

Rev. 5-27-09

FILE NAME =	USER NAME = wlgroendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-55 (STEVENSON EXPRESSWAY) SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cdpw...work\p1201\wlgroendp\0125109-Design.dgn		DRAWN -	REVISED -			55	2007-018I	COOK	14	3	
		CHECKED -	REVISED -			CONTRACT NO. 60C73					
		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.