

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2007-039I	COOK	15	7

CONTRACT: 60D27

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R FULL DEPTH (SQ YD)	SIDEWALK 5" R&R (SQ FT) 18" CARRIAGE	SIDEWALK 5" R&R (SQ FT) 5' PARALLEL	DRIVEWAY 8" R&R (SQ FT)	SALT TOLERANT SODDING (SQ YD)	REMARKS
6841 S. Karlov	5.0	0.8	0.0	0.0	0.0	0.8	
6645 S. Karlov	12.0	2.0	3.0	0.0	0.0	1.7	
5532 S. Karlov	5.0	0.8	7.5	0.0	0.0	0.0	
6050 S. Karlov	7.0	1.2	0.0	0.0	0.0	1.2	Westside By Park
6243 S. Karlov	5.0	0.8	0.0	0.0	0.0	0.8	Near Alley
7939 S. Karlov	5.0	0.8	0.0	0.0	0.0	0.8	
7949 S. Karlov	5.0	0.8	0.0	0.0	0.0	0.8	
7865 S. Karlov	6.0	1.0	0.0	0.0	0.0	1.0	
6406 S. Kedvale	10.0	1.7	0.0	0.0	0.0	1.7	
6824 S. Kedvale	0.0	0.0	42.0	0.0	0.0	0.0	Carraige walk only curb Ok
5945 S. Kedvale	5.0	0.8	7.5	0.0	0.0	0.0	
6242 S. Kedvale	5.0	0.8	7.5	0.0	0.0	0.0	
7939 S. Kedvale	5.0	0.8	0.0	0.0	0.0	0.8	
5900 S. Kolmar	10.0	1.7	0.0	0.0	0.0	1.7	Adj to Sewer
6027 S. Kolmar	5.0	0.8	0.0	0.0	0.0	0.8	Adj to Sewer
6046 S. Kolmar	6.0	1.0	0.0	0.0	0.0	0.8	Adj to Sewer
7817 S. Kolmar	10.0	1.7	0.0	0.0	0.0	1.7	Adj to Sewer
7845 S. Kilpatrick	5.0	0.8	7.5	0.0	0.0	0.0	
7821 S. Kilpatrick	10.0	1.7	0.0	0.0	15.0	0.0	
6331 S Kilpatrick	5.0	0.8	7.5	0.0	0.0	0.0	Carriage walk sunk
7801 S. Kilpatrick	6.0	1.0	0.0	0.0	0.0	1.0	
7210 S. Hamlin	10.0	1.7	3.0	0.0	0.0	1.3	
7138 S. Hamlin	5.0	0.8	7.5	0.0	0.0	0.0	
7128 S. Hamlin	5.0	0.8	7.5	0.0	0.0	0.0	
7248 S. Hamlin	5.0	0.8	7.5	0.0	0.0	0.0	
7112 - 7158 S. Hamlin (Church Side)	200.0	33.3	0.0	1000.0	0.0	0.0	In Front of Church
7232 S. Ridgeway	5.0	0.8	7.5	0.0	0.0	0.0	
7230 S. Ridgeway	5.0	0.8	0.0	0.0	0.0	0.8	
7222 S. Lawndale	5.0	0.8	7.5	0.0	0.0	0.0	
7209 S. Lawndale	5.0	0.8	7.5	0.0	0.0	0.0	
7154 S. Lawndale	5.0	0.8	0.0	0.0	0.0	0.8	
7122 S. Springfield	5.0	0.8	7.5	0.0	0.0	0.0	
6732 S. Springfield	5.0	0.8	7.5	0.0	0.0	0.0	
5939 S. Springfield	10.0	1.7	0.0	0.0	0.0	0.0	
7245 S. Avers	5.0	0.8	7.5	0.0	0.0	0.0	
7215 S. Avers	5.0	0.8	0.0	0.0	0.0	0.8	
4146 W. 56th Pl	10.0	1.7	0.0	0.0	0.0	1.7	
4029 W 56th Pl	10.0	1.7	6.0	0.0	0.0	1.0	
3924 57th PL	5.0	0.8	0.0	0.0	0.0	0.8	Near Driveway - Curb behind Type 1 Structure
SUB-TOTAL	437.0	72.8	159.0	1000.0	15.0	23.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES