

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		WILL Y032-1F	DUPAGE Y032-1F	COOK Y032-1F	CODE NO	ITEM	UNIT		WILL Y032-1F	DUPAGE Y032-1F	COOK Y032-1F
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	6.2	2.1	0.7	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.69	0.23	0.08
67100100	MOBILIZATION	L SUM	1	0.69	0.23	0.08			HOUR	500	500		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.69	0.23	0.08							
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	0.69	0.23	0.08							
81300960	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 42" X 36" X 12"	EACH	4	4	0	0							
X0326459	HANDHOLE, COMPOSITE CONCRETE, 30" X 48"	EACH	22	22	0	0							
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	34584	31691	2552	341							
X0323898	CLOSED CIRCUIT TELEVISION DOME CAMERA	EACH	39	27	9	3							
X0323914	FIBER OPTIC CABLE SPLICE - LATERAL	EACH	5	5	0	0							
X0323957	FIBER OPTIC CABLE SPLICE - MAINLINE	EACH	1	1	0	0							
X0326460	CLOSED CIRCUIT TELEVISION EQUIPMENT, WIRELESS DISTRIBUTION	EACH	34	22	9	3							
X0326461	CLOSED CIRCUIT TELEVISION EQUIPMENT, FIBER OPTIC DISTRIBUTION	EACH	5	5									
X0326463	WIRELESS VIDEO DISTRIBUTION SYSTEM	L SUM	1	0.69	0.23	0.08							
X0326465	MODIFICATION OF EXISTING VIDEO DISTRIBUTION SYSTEM	L SUM	1	0.69	0.23	0.08							
X0324794	COMMUNICATIONS SHELTER, 10.0' X 12.0'	EACH	1	1	0	0							
X0326464	CLOSED CIRCUIT TELEVISION CAMERA STRUCTURE, 80 FT. MOUNTING HEIGHT	EACH	39	27	9	3							
X0325040	FIBER OPTIC INNERDUCT 1 1/4" DIA.	FOOT	47740	47740	0	0							
X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	13	10	3	0							
81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., GALVANIZED STEEL PVC COATED	FOOT	220	220	0	0							
81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL PVC COATED	FOOT	275	275	0	0							
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	715	550	165	0							
X8160162	UNIT DUCT, 2-1/C NO. 8, 1/C NO. 10 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	11803	8228	3135	440							
X8710028	FIBER OPTIC CABLE 6 FIBERS, SINGLE MODE	FOOT	1380	1380	0	0							
X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	48740	48740	0	0							
89502200	MODIFY EXISTING CONTROLLER	EACH	26	16	7	3							
81018600	CONDUIT PUSHED, 2 1/2" DIAMETER, GALVANIZED STEEL	FOOT	1364	517	748	99							
81018900	CONDUIT PUSHED, 4" DIAMETER, GALVANIZED STEEL	FOOT	946	946	0	0							
XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	39	27	9	3							
X0326462	BUDGETARY ALLOWANCE FOR TOLLWAY FIBER OPTIC CONNECTION	L SUM	1	0.69	0.23	0.08							

G 20076600 TRAINEES
 X0326641 INSTALLATION OF CCTV CAMERA
 STRUCTURE IN ROCK FOOT 150 108 36 12
 X0326642 INSTALLATION OF CCTV CAMERA
 STRUCTURE IN SOIL FOOT 312 216 72 24
 B1701155 ELECTRIC CABLE IN CONDUIT, 600V
 (EPR-TYPE USE) 1/C NO. 4/0 FOOT 1600 1600

© 2008

Rev. 5-28-09