

SUMMARY OF QUANTITIES					50% STATE 50% VILLAGE				SUMMARY OF QUANTITIES					50% STATE 50% VILLAGE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 1000-2A	CONSTRUCTION TYPE CODE				CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 1000-2A	CONSTRUCTION TYPE CODE					
					STATE 50% Y031-1F	VILLAGE OF MATTESON 50% Y031-1F	VILLAGE OF MATTESON 100% Y031-3D								STATE 50% Y031-1F	VILLAGE OF MATTESON 50% Y031-1F	VILLAGE OF MATTESON 100% Y031-3D		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	18	18					44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	47	47						
20200100	EARTH EXCAVATION	CU YD	1210	1210					48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5	5						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	2.5	2.5					60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3						
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	280	280					60253100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4					60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4					60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4					60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	6	6						
25100630	EROSION CONTROL BLANKET	SQ YD	280	280					*60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2025	2025						
25200110	SODDING, SALT TOLERANT	SQ YD	280	280					60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	480	480						
25200200	SUPPLEMENTAL WATERING	UNIT	3	3					60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3630	3630						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	6	6					*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	112	112						
28000400	PERIMETER EROSION BARRIER	FOOT	200	200					*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1						
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2428	2428					*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1						
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	1601	1601					63200310	GUARDRAIL REMOVAL	FOOT	162	162						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
40600300	AGGREGATE (PRIME COAT)	TON	8	8					67100100	MOBILIZATION	L SUM	1	1						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1.5	1.5					70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1						
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	307	307					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	142	142					70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6		3	3				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	32	32					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	755	755						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	614	614					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364	364						
42001300	PROTECTIVE COAT	SQ YD	1061	1061					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5060	5060						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	424	424					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1935	1935						
42400800	DETECTABLE WARNINGS	SQ FT	48	48					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	245	245						
44000100	PAVEMENT REMOVAL	SQ YD	467	467					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	155	155						
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	3717	3717					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3825	3825						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2807	2807					*72000200	SIGN PANEL - TYPE 2	SQ FT	53.76		26.88	26.88				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	187	187					*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364	364						
44003100	MEDIAN REMOVAL	SQ FT	9362	9362															
44004250	PAVED SHOULDER REMOVAL	SQ YD	730	730															
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	75	75															
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	65	65															

* SPECIALTY ITEMS