F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	(19 & 20) LS-5	LAKE	17	14
STA. 10+750		TO STA. 11+450		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT 60F55

N

OAKWOOD ROAD

IL. RTE. 22

3 RIVER BIRCH, 7 M O.C.

BIT. PARKING

TIMBER WALL

DETENTION BASIN

3 HACKBERRY, 16 M O.C.

5 BUR OAK, 10 M O.C.

5 HACKBERRY, 8 M O.C.

7 SHINGLE OAK, 8 M O.C.

MATCH LINE STA. 10+750

MATCH LINE STA. 11+100

10+750 10+800 10+850 10+900 10+950 11+000 11+050

3 SERVICEBERRY, 6 M O.C.

4 RED JEWEL CRABAPPLE, 7 M O.C.

55 RED CHOKEBERRY, 1 M O.C., 2 ROWS STAGGERED

20 RED CHOKEBERRY, 1 M O.C., 2 ROWS STAGGERED

5 THORNLESS COCKSPUR HAWTHORN

60 ARROWWOOD VIBURNUM, 1 M O.C., 2 ROWS STAGGERED

60 RED CHOKEBERRY, 1 M O.C., 2 ROWS STAGGERED

40 ARROWWOOD VIBURNUM, 1 M O.C., 2 ROWS STAGGERED

15 ARROWWOOD VIBURNUM, 1 M O. SINGLE ROW

TELSER ROAD

OLD MILL GROVE ROAD

3 VALLEY FORGE ELM, 8 M O.C.

3 RED JEWEL CRABAPPLE, 6 M O.C., STAGGERED

3 RED JEWEL CRABAPPLE, 6 M O.C., STAGGERED

4 THORNLESS COCKSPUR, 6 M O.C., STAGGERED

13 AUSTRIAN PINE, 6 M O.C.

IL. RTE. 22

4 CATALPA, 8 M O.C.

1 REPLACE WITH 2 SARGENT CRABAPPLE, 7 M O.C., STAGGERED

5 BUR OAK, 8 M O.C.

MATCH LINE STA. 11+100

MATCH LINE STA. 11+450

11+100 11+150 11+200 11+250 11+300 11+350 11+400

3 VALLEY FORGE ELM, 8 M O.C.

5 RED JEWEL CRABAPPLE, 11 M O.C.

KNOX PARK

1 PROPOSED DETENTION BASIN

1 DELETE ~~5 VALLEY FORGE ELM, 8 M O.C.~~ REPLACE WITH 2 SARGENT CRABAPPLE, 7 M O.C., STAGGERED

1 DELETE ~~5 HACKBERRY, 10 M O.C.~~ REPLACE WITH 6 ADAMS CRABAPPLE, 7 M O.C., STAGGERED

5 m 0 20 m

1 : 500

REVISIONS	
NAME	DATE
1 REVISION 1	5-22-09

ILLINOIS DEPARTMENT OF TRANSPORTATION

IL. RTE. 22:
W/O US 12 (RAND RD.) TO
E/O QUENTIN RD.

LANDSCAPING PLANS

SCALE 1:500 DRAWN BY

DATE 3/12/09 CHECKED BY