



| CODE NUMBER | PAY ITEM | UNIT | TOTAL QUANTITY | | CONSTRUCTION TYPE CODES | | | |
|---------------------|---|-------------------|----------------|--------------|-------------------------|--|--|--|
| | | | | J000-2A | | | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 905 | 905 | | | | |
| 44201741 | CLASS D PATCHES, TYPE II, 8 INCH | SQ YD | 1,000 | 1,000 | | | | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 29 | 29 | | | | |
| 44201745 | CLASS D PATCHES, TYPE III, 8 INCH | SQ YD | 1,000 | 1,000 | | | | |
| 44001980 | CONCRETE BARRIER REMOVAL | FOOT | 552 | 552 | | | | |
| 44201747 | CLASS D PATCHES, TYPE IV, 8 INCH | SQ YD | 1,000 | 1,000 | | | | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 11,305 | 11,305 | | | | |
| 44300200 | STRIP REFLECTIVE CRACK CONTROL TREATMENT | FOOT | 1,552 | 1,552 | | | | |
| 48101620 | AGGREGATE SHOULDERS, TYPE B 10" | SQ YD | 112 | 112 | | | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 1,362 | 1,362 | | | | |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8" | SQ YD | 1,035 | 1,035 | | | | |
| 48203045 | HOT-MIX ASPHALT SHOULDERS, 12" | SQ YD | 14,211 | 14,211 | | | | |
| 48300500 | PORTLAND CEMENT CONCRETE SHOULDERS 10" | SQ YD | 282 | 282 | | | | |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | EACH | 5 | 5 | | | | |
| 54214719 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24" | EACH | 2 | 2 | | | | |
| 54247130 | GRATING FOR CONCRETE FLARED END SECTION 24" | EACH | 5 | 5 | | | | |
| 54248130 | GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24" | EACH | 2 | 2 | | | | |
| 55034300 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19 | FOOT | 325 | 325 | | | | |
| 55101200 | STORM SEWER REMOVAL 24" | FOOT | 101 | 101 | | | | |
| 60107700 | PIPE UNDERDRAINS 6" | FOOT | 1,766 | 1,766 | | | | |
| 60108200 | PIPE UNDERDRAINS 6" (SPECIAL) | FOOT | 18 | 18 | | | | |
| 60201340 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE | EACH | 6 | 6 | | | | |
| 60205040 | CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE | EACH | 4 | 4 | | | | |
| 60221700 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE | EACH | 1 | 1 | | | | |
| 60614600 | PAVED DITCH (SPECIAL) | FOOT | 365 | 365 | | | | |
| *63000001 | STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS | FOOT | 67 | 67 | | | | |
| *63100075 | TRAFFIC BARRIER TERMINAL, TYPE 5A | EACH | 1 | 1 | | | | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 50 | 50 | | | | |
| 63200400 | CABLE ROAD GUARD REMOVAL | FOOT | 9,742 | 9,742 | | | | |
| 63500105 | DELINEATORS | EACH | 92 | 92 | | | | |
| 63700255 | CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT | FOOT | 1,739 | 1,739 | | | | |
| 63700900 | CONCRETE BARRIER BASE | FOOT | 1,739 | 1,739 | | | | |
| 66400105 | CHAIN LINK FENCE, 4' | FOOT | 865 | 865 | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 8 | 8 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 | | | | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 16 | 16 | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 27,394 | 27,394 | | | | |

* SPECIALTY ITEMS

* Specialty Items

McDonough Associates Inc.
 Engineers / Architects
 130 East Randolph Street, Chicago, Illinois 60601

| | | | |
|--------------------------------------|-----------------------|-----------------|-----------|
| FILE NAME = D160F71-SHT-S0002.dgn | USER NAME = TKIuegal | DESIGNED - TRK | REVISED - |
| PLOT SCALE = 1:50 | PLOT DATE = 3/20/2009 | DRAWN - TRK | REVISED - |
| | | CHECKED - DLT | REVISED - |
| | | DATE - 03/20/09 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 4 SHEETS STA. TO STA.

| | | | | |
|---|------------|--------|--------------------|--------------|
| F.A.I RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 55 | 99-2HB-2-R | WILL | 171 | 5 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 60F71 | |

Rev. 5-26-09

FINAL