

EARTHWORK SCHEDULE I-55

BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
1078+00.00	1079+00.00	23	75	20	5	15	0
1079+00.00	1080+00.00	19	75	15	5	10	0
1080+00.00	1081+00.00	5	20	5	0	5	0
1081+00.00	1082+00.00	11	50	10	0	10	0
1082+00.00	1083+00.00	15	75	15	5	10	0
1083+00.00	1084+00.00	15	50	15	10	5	0
1084+00.00	1085+00.00	15	20	15	10	5	0
1085+00.00	1086+00.00	15	10	15	5	10	0
1086+00.00	1087+00.00	15	0	15	0	15	0
1087+00.00	1088+00.00	15	0	15	0	15	0
1088+00.00	1089+00.00	15	20	15	0	15	0
1089+00.00	1090+00.00	17	40	15	0	15	0
1090+00.00	1091+00.00	21	40	20	0	20	0
1091+00.00	1092+00.00	23	40	20	0	20	0
1092+00.00	1093+00.00	23	40	20	0	20	0
1093+00.00	1094+00.00	23	40	20	0	20	0
1094+00.00	1095+00.00	23	40	20	0	20	0
1095+00.00	1096+00.00	23	40	20	0	20	0
1096+00.00	1096+30.00	19	40	15	0	15	0
1096+30.00	1097+00.00	15	20	15	0	15	0
1097+00.00	1098+00.00	15	0	15	0	15	0
1098+00.00	1099+00.00	17	0	15	0	15	0
1099+00.00	1100+00.00	19	0	15	0	15	0
1100+00.00	1101+00.00	19	20	15	0	15	0
1101+00.00	1102+00.00	19	40	15	0	15	0
1102+00.00	1103+00.00	10	20	10	0	10	0
1103+00.00	1104+00.00	0	0	0	0	0	0
1104+00.00	1105+00.00	0	0	0	0	0	0
1105+00.00	1106+00.00	0	0	0	0	0	0
1106+00.00	1107+00.00	0	0	0	0	0	0
1107+00.00	1108+00.00	0	0	0	0	0	0
1108+00.00	1109+00.00	0	0	0	0	0	0
1109+00.00	1110+00.00	0	0	0	0	0	0
1110+00.00	1111+00.00	0	0	0	0	0	0
1111+00.00	1112+00.00	0	0	0	0	0	0
1112+00.00	1113+00.00	0	0	0	0	0	0
1113+00.00	1114+00.00	0	0	0	0	0	0
1114+00.00	1115+00.00	0	0	0	0	0	0
1115+00.00	1116+00.00	0	0	0	0	0	0
1116+00.00	1117+00.00	0	0	0	0	0	0
1117+00.00	1118+00.00	0	0	0	0	0	0
1118+00.00	1119+00.00	0	0	0	0	0	0
SUB TOTAL		2,151	5,670	1,885	225	1,660	0

\* ASSUME 15% FOR SHRINKAGE

McDonough Associates Inc.  
Engineers / Architects  
130 East Randolph Street, Chicago, Illinois 60601

FILE NAME = D:\6071-SHT-SCHEDULE02.dgn	USER NAME = TK\uegal	DESIGNED - TRK	REVISED -
		DRAWN - TRK	REVISED -
PLOT SCALE = 1:50		CHECKED - DLT	REVISED -
PLOT DATE = 3/19/2009		DATE - 03/20/09	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-2HB-2-R	WILL	171	11
CONTRACT NO. 60F71				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

FINAL