SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES 100% STATE	CONSTRUCTION TYPE CODE: TRUCK SCALES (FIXED) Y222					
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9					
25100115	MULCH, METHOD 2	ACRE	0.1	0.1					
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	55	55					
31200100	STABILIZED SUB-BASE 4"	SQ YD	73	73					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	16	16					
44000100	PAVEMENT REMOVAL	SQ YD	16	16					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	153	153					
44000700	APPROACH SLAB REMOVAL	SQ YD	54	54					
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	22	22					
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	29	29					
44213100	PAVEMENT FABRIC	SQ YD	51	51					
44213200	SAW CUTS	FOOT	24	24					
50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1	1					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25	25					
50300300	PROTECTIVE COAT	SQ YD	270	270					
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1					
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9860	9860					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	63	63					
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	90	90					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
*78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	450	450					
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	90	90					
87900200	DRILL EXISTING HANDHOLE	EACH	1	1					
88500500	INDUCTION LOOP DETECTOR AMPLIFIER	EACH	1	1					
88600100	DETECTOR LOOP, TYPE I	FOOT	34	34					
X0324265	JACK REMOVE AND REPLACE LOAD CELLS	L SUM	1	1					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	52	52					

SUMMARY OF QUANTITIES

CODE NO	ITEM	URBAN UNIT 100% STATE	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: TRUCK SCALES (FIXED) Y222					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
42001400	BRIDGE APPROACH PAVEMENT SPECIAL	SQ YD	54	54					
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	97	97					
Z0017202	DOWEL BARS 1 1/2"	EACH	20	20					
Z0075310	TIE BARS 3/4"	EACH	79	79					
	* SPECIALTY ITEM								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	44	44					
44000600	SIDEWALK REMOVAL	SQ FT	44	44					
44003100	MEDIAN REMOVAL	SQ FT	135	135					
44004250	PAVED SHOULDER REMOVAL	SQ YD	2	2					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2	2					
60626300	STABILIZED MEDIAN SURFACE	SQ YD	15	15					
*78008270	POLYUREA PAVEMENT MARKING TYPE I-LINE 24"	FOOT	24	24					
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	90	90					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	6	6					

FILE NAME = c:\pw_work\pwidot\kellers\d0131400\D134609-Design.dgn	USER NAME = kellers	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/23/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERSTATE 55 (NB BOLINGBROOK WEIGH STATION)
SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2009-017 I	WILL	16	3

CONTRACT NO. 60G16

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT