

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	COOK	WILL					TOTAL QUANTITIES				
				COUNTY 1000	COUNTY 1000									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	5	4									
40600300	AGGREGATE (PRIME COAT)	TON	39	23	16									
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	58	34	24									
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.6	0.4									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	877	567	310									
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2135	1267	868									
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	19,048	11298	7750									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2									
67100100	MOBILIZATION	L SUM	1	0.6	0.4									
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	13395	13395										
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5966	5581	385									
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35,812	27,869	7,943									
*78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	13395	13395										
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1048	606	442									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1048	606	442									
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1										
XD325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.6	0.4									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1155		1155									
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1		1									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1									



\* SPECIALTY ITEM

Rev. 5-27-09