SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6					
40600300	AGGREGATE (PRIME COAT)	TON	27	27					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	659	659					
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1475	1475					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	13167	13167					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	115	115					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	406	406					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	106	106					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	178	178					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	3198	3198					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1333	1333					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22928	22928					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1350	1350					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	165	165					
*78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	3198	3198					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	308	308					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	308	308					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	600	600					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

FILE NAME = c:\pw_work\pwidot\wilgreendp\d0125109\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/24/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

VARIOUS INTERSTATE RAMPS
SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-028 PP	DUPAGE	27	3

CONTRACT NO. 60G27

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 3/24/2009 12:28:24 PM User=wilgreendp