ROUTE: NB Gary Ave. (Travis to Elgin-O'Hare entrance ramp) - HMA SURFACE

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
Travis	Elgin-O'Hare Entrance	NB	1	12	6	72	8
	Ramp		2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
		Joint Repair		2	200	400	44
			1	20	6	120	13
			1	20	6	120	13
			1	20	6	120	13
			1	12	30	360	40
			1	12	6	72	8
			1	12	30	360	40
			1	20	6	120	13
			1	20	6	120	13
			1	20	6	120	13
			1	20	6	120	13
			1	20	6	120	13
			1	20	6	120	13
		Joint Repair		2	200	400	44
			1	20	80	1600	178
		TOTALS:			822 FT		771 SY

ROUTE: SB Gary Ave. (Travis to Elgin-O'Hare Exit Ramp) - HMA SURFACE

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
Travis	Elgin-O'Hare Exit Ramp	SB	1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
		Joint Repair		2	200	400	44
			1	13	6	78	9
			1	13	6	78	9
			1	13	6	78	9
		Joint Repair		2	20	40	4
			1	13	6	78	9
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
		TOTALS:			346 FT		226 SY

FILE NAME = c:\pw_work\pwidot\wilgreendp\d0125109\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/24/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
GARY AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-028 PP	DUPAGE	27	6

CONTRACT NO. 60G27

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 3/24/2009 12:29:18 PM User=wilgreendp