ROUTE: Exit Ramp (SB I-355 to Army Trail Rd.) - PCC SURFACE

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Off Ramp	Off Ramp	SB	1	16	10	160	18
		SB	1	20	2	40	4
		SB	1	16	2	32	4
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	8	96	11
		SB	1	12	2	24	3
		SB	1	12	6	72	8
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	12	2	24	3
		SB	1	2	300	600	67
		SB	2	12	15	180	20
		SB	2	12	5	60	7
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	5	60	7
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	4	48	5
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	12	2	24	3
		SB	2	2	500	1000	111
		SB	3	12	15	180	20
		SB	3	12	5	60	7
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	5	60	7
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	5	60	7
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		SB	3	12	2	24	3
		TOTALS:			969 FT		410 SY

FILE NAME = c:\pw_work\pwidot\wilgreendp\d0125109\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/24/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
I-355 EXIT RAMP

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-028 PP	DUPAGE	27	13
		CONTRACT NO. 60G27		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 3/24/2009 12:49:29 PM User=wilgreendp