

URBAN
100%
STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	COOK COUNTY I000	DUPAGE COUNTY I000
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	1.9	0.1
40600300	AGGREGATE (PRIME COAT)	TON	15	14	1
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	23	22	1
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.9	0.1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	217	206	11
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	486	461	25
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	4337	4110	227
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	2.8	0.2
67100100	MOBILIZATION	L SUM	1	0.9	0.1
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	2100	1995	105
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	875	831	44
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6827	6487	340
*78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	2100	1995	105
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	210	200	10
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	210	200	10
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.9	0.1
	X0325702 NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES		



X0325702 NIGHTTIME WORK ZONE LIGHTING

Rev. 5-27-09

FILE NAME =	USER NAME = wlgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-290 (EISENHOWER EXPRESSWAY) SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\wlgreendp\02090300.dwg		DRAWN -	REVISED -			290	2009-030 PP	COOK & DUP.	15	3	
PLOT SCALE = 100.0000' / 1" IN.		CHECKED -	REVISED -			CONTRACT NO. 60C29					
PLOT DATE = 3/14/2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.