

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 332	0101.1 I-3	COOK	11	3

CONTRACT NO: 60G33

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL J.U.L.I.E. AT (800)892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES (48 HOURS NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 FOR EXPRESSWAYS AND (847) 705-4470 FOR ARTERIALS A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UPMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECTION.

THE "ARTERIAL ROAD INFORMATION SIGN" (TC-22) DETAIL IS APPLICABLE ONLY TO ARTERIAL ROADS AND SHALL NOT BE APPLIED TO EXPRESSWAYS.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM BRIDGE INSPECTORS.

THE CONTRACTOR SHALL SALVAGE AND RETURN THE EXISTING STEEL CARRIER BEAM (W33 X 130, ±71 FT LONG) TO:

DISTRICT BRIDGE OFFICE
1101 BIESTERFIELD RD.
ELK GROVE VILLAGE, IL 60007

CONTACT SHAKER ASFOUR AT (847) 956-1501. IF CARRIER BEAMS NEED TO BE DISASSEMBLED FOR TRANSPORT, THE BEAMS SHALL BE UNBOLTED AND SPLICE PLATES SALVAGED; FLAME CUTTING OF BEAM IS NOT ALLOWED. THIS WORK SHALL INCLUDE REMOVING, TRANSPORTING, AND UNLOADING THE EXISTING CARRIER BEAM TO THE ABOVE YARD WHICH COST IS INCLUDED IN THE COST OF "STRUCTURAL STEEL REMOVAL".

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES