

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7, SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = gaglianobt	DESIGNED ~	REVISED -	R. MIRS 09-15-97					F.A.P. RTE.	SECTION	COUNTY TOTAL SHEET			
Vi\diststd\22x34\to22.dgn		DRAWN ~	REVISED -	R. MIRS 12-11-97	STATE OF ILLINOIS				332	0101.1 1-3	COOK 11 11			
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED -	T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION						TC-22	CONTRACT NO.		
	PLOT DATE = 1/4/2008	DATE -	REVISED -	C. JUCIUS 01-31-07		SCALE: NONE	SCALE, NOME SHEET NO. 1 OF 1 SHEETS STA. TO STA.				TO STA.	FED. ROA	D. ROAD DISY, NO. 1 ILLINOIS FED. AID PROJECT	