

SUMMARY OF QUANTITIES			URBAN	FED/ST/CHICAGO HEIGHTS				FED/ST		FED/ST/CHICAGO HEIGHTS		FED/ST	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90/10	CONSTRUCTION TYPE CODE				90/10	90/5/5		90/10	
				US.30 @ STATE ST.	US.30 @ WENTWOTH AVE.	90/5/5 @ CENTER AVE.	90/5/5 @ EAST END AVE.	US.30 @ HALSTED ST.	US.30 @ ILL. RTE. 1	ILL. RTE. 1 @ 16TH STREET.	ILL. RTE. 1 @ 15TH STREET	ILL. RTE. 1 @ DIXIE HIGHWAY	INTERCONNECT ILL. RTE. 1 (CHICAGO RD.)
			Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	42					26	16				
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	132	10		10	8	10				94	
81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	10						10				
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	4567	324	603	210	618	1221	1306			285	
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	212				145					67	
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	80									80	
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1669	249	152	198	134	394	326			216	
81400100	HANDHOLE	EACH	40	7	5	5	4	6	7			6	
81400200	HEAVY-DUTY HANDHOLE	EACH	18	4	2		1	4	4			3	
81400300	DOUBLE HANDHOLE	EACH	10	1	1	1	1	2	2			2	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2003	762	38	378	14	34	160			617	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3			1				1	1		
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	8	1	1	1	1	1		1	1	1	
85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1						1				
86000105	MASTER CONTROLLER (SPECIAL)	EACH	1						1				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	3						1	1	1		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3472		610	450	469	636	667			640	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	6512	300	869	826	639	1314	1670			894	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	10922	1438	1379	1701	1852	1434	1662			1456	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	7094	1445	527		237	1440	895			2550	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	12539	2089	1129	860	986	2292	3083			2100	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	774		108	117	48	180	234			87	
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4			1	3						
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5	1	2				2				
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	4		2							2	
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1			1							